



INSTRUMENT APPROACH PROCEDURE CHARTS



IFR ALTERNATE AIRPORT MINIMUMS

Standard alternate minimums for non-precision approaches and approaches with vertical guidance [NDB, VOR, LOC, TACAN, LDA, SDF, VOR/DME, ASR, RNAV (GPS) or RNAV (RNP)] are 800-2. Standard alternate minimums for precision approaches (ILS, PAR, or GLS) are 600-2. Airports within this geographical area that require alternate minimums other than standard or alternate minimums with restrictions are listed below. NA - means alternate minimums are not authorized due to unmonitored facility, absence of weather reporting service, or lack of adequate navigation coverage. Civil pilots see FAR 91. IFR Alternate Minimums: Ceiling and Visibility Minimums not applicable to USA/USN/USAF. Pilots must review the IFR Alternate Minimums Notes for alternate airfield suitability.

NAME ALTERNATE MINIMUMS

AHOSKIE, NC

TRI-COUNTY (ASJ) RNAV (GPS) Rwy 1
RNAV (GPS) Rwy 19
VOR/DME-A

NA when local weather not available.
Category D, 800-2½.

ALBEMARLE, NC

STANLY
COUNTY (VUJ) ILS or LOC Rwy 22L¹²
NDB Rwy 22L¹
RNAV (GPS) Rwy 4R
RNAV (GPS) Rwy 22L

NA when local weather not available.
¹NA when control tower closed.
²ILS, Categories A, B, C, D, 700-2.

ALLENDALE, SC

ALLENDALE
COUNTY (AQX) RNAV (GPS) Rwy 17
RNAV (GPS) Rwy 35
VOR-A

NA when local weather not available.

ANDERSON, SC

ANDERSON
RGNL (AND) ILS or LOC Rwy 5¹
RNAV (GPS) Rwy 5¹
RNAV (GPS) Rwy 17¹²
RNAV (GPS) Rwy 23²
RNAV (GPS) Rwy 35¹²
VOR Rwy 5¹

¹NA when local weather not available.
²Category D, 800-2½.

ASHEBORO, NC

ASHEBORO
RGNL (HBI) RNAV (GPS) Rwy 3
RNAV (GPS) Rwy 21

Categories C, D, 1100-3.

NAME ALTERNATE MINIMUMS

ASHEVILLE, NC

ASHEVILLE
RGNL (AVL) ILS or LOC Rwy 35¹²
RNAV (GPS) Rwy 17³
RNAV (GPS) Rwy 35³

¹NA when control tower closed.
²ILS, LOC, Categories A, B, 1000-2; Category C, 1200-3; Category D, 1500-3.
³Category C, 1200-3; Category D, 1500-3.

BARNWELL, SC

BARNWELL
RGNL (BNL) RNAV (GPS) Rwy 17
NA when local weather not available.

BEAUFORT, NC

MICHAEL J.
SMITH FIELD (MRH) RNAV (GPS) Rwy 3
RNAV (GPS) Rwy 8
RNAV (GPS) Rwy 14
RNAV (GPS) Rwy 21
RNAV (GPS) Rwy 26
RNAV (GPS) Rwy 32

NA when local weather not available.

BEAUFORT, SC

BEAUFORT
COUNTY (ARW) RNAV (GPS) Rwy 7
RNAV (GPS) Rwy 25

NA when local weather not available.

BENNETTSVILLE, SC

MARLBORO COUNTY JETPORT-H E AVENT
FIELD (BBP) RNAV (GPS) Rwy 7
RNAV (GPS) Rwy 25

NA when local weather not available.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017





ALTERNATE MINS

17257

M2



NAME ALTERNATE MINIMUMS

BURLINGTON, NC

BURLINGTON-ALAMANCE
 RGNL (BUY)..... RNAV (GPS) Rwy 6¹
 RNAV (GPS) Rwy 24¹
 VOR/DME-A

NA when local weather not available.
¹Category C, 1000-2³/₄; Category D, 1000-3.

CHARLESTON, SC

CHARLESTON
 AFB/INTL (CHS)..... ILS or LOC Rwy 15¹
 ILS or LOC/DME Rwy 33¹
 VOR/DME or TACAN Rwy 3²
 VOR/DME or TACAN Rwy 21²

¹ILS, Category E, 700-2¹/₂; LOC, Category E,
 800-2¹/₂.
²Category E, 800-2¹/₂.

CHARLESTON
 EXECUTIVE (JZI)..... ILS or LOC Rwy 9
 RNAV (GPS) Rwy 4
 RNAV (GPS) Rwy 9
 RNAV (GPS) Rwy 27

NA when local weather not available.

CHARLOTTE, NC

CHARLOTTE/DOUGLAS
 INTL (CLT) ILS or LOC Rwy 18L²
 ILS or LOC Rwy 18R²
 ILS or LOC Rwy 23¹
 ILS or LOC Rwy 36L²
 ILS or LOC Rwy 36R²
 RNAV (GPS) Y Rwy 18L³
 RNAV (GPS) Y Rwy 18R³
 RNAV (GPS) Y Rwy 36L³
 RNAV (GPS) Y Rwy 36R³

¹ILS, Categories A, B, C, D, 700-2.
²ILS, LOC, Category C, 800-2¹/₄; Category D,
 800-2¹/₂.
³Category C, 800-2¹/₄; Category D, 800-2¹/₂.

CHERAW, SC

CHERAW MUNI/LYNCH BELLINGER
 FIELD (QOW)..... RNAV (GPS) Rwy 26
 VOR/DME Rwy 8

NA when local weather not available.
 Category C, 900-2¹/₂; Category D, 900-2³/₄.

CHESTER, SC

CHESTER CATAWBA
 RGNL (DCM)..... NDB Rwy 35¹
 RNAV (GPS) Rwy 17
 RNAV (GPS) Rwy 35

NA when local weather not available.
¹Category D, 800-2¹/₄.

NAME ALTERNATE MINIMUMS

CLEMSON, SC

OCONEE COUNTY
 RGNL (CEU) NDB Rwy 25
 RNAV (GPS) Rwy 7¹
 RNAV (GPS) Rwy 25¹

NA when local weather not available.
¹Category C, 800-2¹/₄.

CLINTON, NC

CLINTON-SAMPSON
 COUNTY (CTZ) LOC Rwy 6
 RNAV (GPS) Rwy 6
 RNAV (GPS) Rwy Y 24
 RNAV (GPS) Rwy Z 24
 VOR/DME-A

NA when local weather not available.

COLUMBIA, SC

COLUMBIA
 METROPOLITAN (CAE) ILS or LOC Rwy 5¹
 ILS or LOC Rwy 11²

¹ILS, Categories A, B, 800-2; Category C, 800-2¹/₄; Category D, 800-2¹/₂; LOC, Category C, 800-2¹/₄; Category D, 800-2¹/₂.
²ILS, Categories C, D, 700-2.

CONCORD, NC

CONCORD
 RGNL (JQF)..... ILS or LOC Rwy 20¹
 RNAV (GPS) Rwy 2²
 RNAV (GPS) Rwy 20¹

NA when local weather not available.
¹Category D, 800-2¹/₂.
²Category C, 800-2¹/₄; Category D, 800-2¹/₂.

CONWAY, SC

CONWAY-HORRY
 COUNTY (HYW) RNAV (GPS) Rwy 4
 RNAV (GPS) Rwy 22

NA when local weather not available.

CURRITUCK, NC

CURRITUCK COUNTY
 RGNL (ONX)..... RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23

NA when local weather not available.

DARLINGTON, SC

DARLINGTON COUNTY
 (UDG) RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 VOR/DME-A

NA when local weather not available.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



ALTERNATE MINS

17257

M2

SE-2





ALTERNATE MINS



NAME ALTERNATE MINIMUMS
EDENTON, NC
 NORTHEASTERN
 RGNL (EDE)..... ILS or LOC Rwy 19
 RNAV (GPS) Rwy 1
 RNAV (GPS) Rwy 19
 NA when local weather not available.

ELIZABETH CITY, NC
 ELIZABETH CITY CG AIR STATION/
 RGNL (ECG) ILS or LOC Rwy 10¹²³
 RNAV (GPS) Rwy 10¹
 RNAV (GPS) Rwy 19¹
 RNAV (GPS) Rwy 28¹
 VOR/DME Rwy 10¹
 VOR/DME Rwy 19¹
 VOR/DME Rwy 28⁴

¹NA when local weather not available.
²ILS, Category D 700-2.
³ILS, LOC, NA when control tower closed.
⁴NA when local altimeter not available.

ELIZABETHTOWN, NC
 CARL L BROWN JR
 FIELD (EYF)..... RNAV (GPS) Rwy 15
 RNAV (GPS) Rwy 33
 VOR/DME Rwy 15
 NA when local weather not available.

ERWIN, NC
 HARNETT RGNL
 JETPORT (HRJ)..... LOC/DME Rwy 5
 RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 NA when local weather not available.

FAYETTEVILLE, NC
 FAYETTEVILLE RGNL/GRANNIS
 FIELD (FAY)..... ILS or LOC Rwy 4²
 RNAV (GPS) Rwy 4³
 RNAV (GPS) Rwy 22³
 VOR Rwy 22¹

¹NA when local weather not available.
²ILS, Category C, 700-2; Category D, 700-2½.
 LOC, Category D, 800-2¼.
³Category D, 800-2¼.

NAME ALTERNATE MINIMUMS
FLORENCE, SC
 FLORENCE
 RGNL (FLO)..... ILS or LOC Rwy 9¹²
 RNAV (GPS) Rwy 1
 RNAV (GPS) Rwy 9
 RNAV (GPS) Rwy 19
 RNAV (GPS) Rwy 27
 VOR or TACAN-A
 NA when local weather not available.
¹ILS, Categories A, B, C, 700-2; Category D,
 700-2¼. LOC, Category D, 800-2¼.
²NA when control tower closed.

FRANKLIN, NC
 MACON COUNTY (1A5) RNAV (GPS)-A
 NA when local weather not available.
 Categories A, B, 1600-2; Category C, 1800-3.

GASTONIA, NC
 GASTONIA MUNI (AKH)..... RNAV (GPS) Rwy 21
 NA when local weather not available.

GEORGETOWN, SC
 GEORGETOWN
 COUNTY (GGE) NDB Rwy 5¹
 RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 NA when local weather not available.
 Category D, 800-2¼.
¹NA when FBO closed.

GOLDSBORO, NC
 WAYNE EXECUTIVE
 JETPORT (GWW)..... ILS or LOC Rwy 23
 RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 VOR-A
 NA when local weather not available.

GREENSBORO, NC
 PIEDMONT TRIAD
 INTL (GSO)..... ILS Y or LOC/DME Y Rwy 32¹
 ILS Z or LOC/DME Z Rwy 32¹
 RNAV (GPS) Rwy 14
 RNAV (GPS) Rwy 32¹
 NA when local weather not available.
¹Category C, 800-2¼; Category D, 800-2½.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



ALTERNATE MINS





ALTERNATE MINS

17257

M4



NAME ALTERNATE MINIMUMS
GREENVILLE, NC
 PITT-
 GREENVILLE (PGV) ILS Y or LOC Y Rwy 20¹
 ILS Z or LOC Z Rwy 20¹
 RNAV (GPS) Rwy 2²
 RNAV (GPS) Rwy 8
 RNAV (GPS) Rwy 20²
 RNAV (GPS) Rwy 26

NA when local weather not available.
¹ILS Category C, 700-2; Category D, 800-2¹/₄.
 LOC, Category D, 800-2¹/₄.
²Category D, 800-2¹/₂.

GREENVILLE, SC
 DONALDSON
 FIELD (GYH) ILS or LOC Rwy 5
 NA when local weather not available.
 NA when control tower closed.

GREENVILLE
 DOWNTOWN (GMU) ILS or LOC Rwy 1¹²³
 ILS Y or LOC Y Rwy 1¹²⁵
 ILS Z or LOC Z Rwy 1¹²⁵
 RNAV (GPS) Rwy 1²⁴
 RNAV (GPS) Rwy 10²⁶
 RNAV (GPS) Rwy 19²⁶
 RNAV (GPS) Rwy 28²⁶
 RADAR-1¹⁴

¹NA when control tower closed.
²NA when local weather not available.
³ILS, Category D, 700-2. LOC, Category D, 800-2¹/₄.
⁴Category D, 800-2¹/₄.
⁵ILS, Category C, 800-2; Category D, 2³/₄; LOC, Category D, 900-2³/₄.
⁶Category D, 900-2³/₄.

GREENWOOD, SC
 GREENWOOD
 COUNTY (GRD) NDB Rwy 27
 RNAV (GPS) Rwy 9
 RNAV (GPS) Rwy 27
 VOR Rwy 9
 NA when local weather not available.
 Category D, 800-2¹/₄.

GREER, SC
 GREENVILLE-SPARTANBURG
 INTL (GSP) ILS or LOC Rwy 4¹
 ILS or LOC Rwy 22¹
 RADAR-1
 RNAV (GPS) Rwy 4
 RNAV (GPS) Rwy 22
 NA when local weather not available.
¹NA when control tower closed.

NAME ALTERNATE MINIMUMS
HICKORY, NC
 HICKORY RGNL (HKY) ILS or LOC Rwy 24¹
 RNAV (GPS) Rwy 1
 RNAV (GPS) Rwy 6
 RNAV (GPS) Rwy 19
 RNAV (GPS) Rwy 24
 NA when local weather not available.
¹NA when control tower closed.

HILTON HEAD ISLAND, SC
 HILTON HEAD (HXD) VOR/DME-A
 Category C, 800-2¹/₄; Category D, 800-2¹/₂.

JACKSONVILLE, NC
 ALBERT J ELLIS (OAJ) ILS or LOC Rwy 5
 RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 NA when local weather not available.

JEFFERSON, NC
 ASHE COUNTY (GEV) RNAV (GPS) Rwy 28
 NA when local weather not available.
 Categories A, B, 1100-2; Categories C, D, 2000-3.

KENANSVILLE, NC
 DUPLIN CO (DPL) RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 NA when local weather not available.

KINGSTREE, SC
 WILLIAMSBURG
 RGNL (CKI) RNAV (GPS) Rwy 14
 RNAV (GPS) Rwy 32
 NA when local weather not available.
 Category C, 900-2³/₄; Category D, 900-3.

KINSTON, NC
 KINSTON RGNL JETPORT AT
 STALLINGS FIELD (ISO) ILS or LOC Rwy 5¹²
 RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 VOR Rwy 23
 NA when local weather not available.
¹NA when control tower closed.
²Categories C, D, 700-2.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



ALTERNATE MINS

17257

M4

SE-2





ALTERNATE MINS

17257

M5



LANCASTER, SC
LANCASTER COUNTY-MC WHIRTER
FIELD (LKR)..... **RNAV (GPS) Rwy 6**
RNAV (GPS) Rwy 24
VOR/DME-A¹

NA when local weather not available.
¹Categories A, B, 900-2; Category C, 900-2½;
Category D, 900-2¾.

LAURENS, SC
LAURENS COUNTY (LUX) .. **RNAV (GPS) Rwy 8**
RNAV (GPS) Rwy 26
NA when local weather not available.

LEXINGTON, NC
DAVIDSON
COUNTY (EXX)..... **RNAV (GPS) Rwy 6**
RNAV (GPS) Rwy 24
VOR/DME Rwy 24
NA when local weather not available.

LINCOLNTON, NC
LINCOLNTON-LINCOLN COUNTY
RGNL (IPJ)..... **ILS Y or LOC Y Rwy 23²³**
ILS Z or LOC Z Rwy 23²³
NDB Rwy 23¹
RNAV (GPS) Rwy 5¹
RNAV (GPS) Rwy 23³
NA when local weather not available.
¹Category C, 800-2¼; Category D, 800-2½.
²NA when FBO closed.
³Category C, 800-2¼; Category D, 800-2½.

LOUISBURG, NC
TRIANGLE NORTH
EXECUTIVE (LHZ) **RNAV (GPS) Rwy 5¹**
RNAV (GPS) Rwy 23¹
VOR/DME-A²
¹NA when local weather not available.
²Category D 800-2-¼.

LUMBERTON, NC
LUBERTON RGNL (LBT) **ILS or LOC Rwy 5**
RNAV (GPS) Rwy 5
RNAV (GPS) Rwy 13
RNAV (GPS) Rwy 23
NA when local weather not available.

MANTEO, NC
DARE COUNTY
RGNL (MQI) **RNAV (GPS) Rwy 5**
RNAV (GPS) Rwy 17
RNAV (GPS) Rwy 23
NA when local weather not available.

MARION, SC
MARION
COUNTY (MAO) **RNAV (GPS) Rwy 4**
RNAV (GPS) Rwy 22
VOR/DME-A

NA when local weather not available.
Category D, 900-2¾.

MAXTON, NC
LAURINBURG-
MAXTON (MEB) **ILS or LOC Rwy 5**
RNAV (GPS) Rwy 5
RNAV (GPS) Rwy 23
NA when local weather not available.

MONROE, NC
CHARLOTTE-MONROE
EXECUTIVE (EQY)..... **RNAV (GPS) Rwy 5**
RNAV (GPS) Rwy 23
Category D, 800-2½.

MORGANTON, NC
FOOTHILLS RGNL (MRN)..... **LOC Rwy 3**
RNAV (GPS) Rwy 3
RNAV (GPS) Rwy 21
NA when local weather not available.

MOUNT AIRY, NC
MOUNT AIRY/SURRY
COUNTY (MWK)..... **RNAV (GPS) Rwy 18**
RNAV (GPS) Rwy 36
NA when local weather not available.
Category C, 900-2½; Category D, 1000-3.

MOUNT PLEASANT, SC
MT PLEASANT RGNL-
FAISON FIELD (LRO)..... **RNAV (GPS) Rwy 17**
RNAV (GPS) Rwy 35
VOR/DME-A
NA when local weather not available.

MYRTLE BEACH, SC
MYRTLE BEACH
INTL (MYR)..... **ILS or LOC Rwy 18¹**
ILS or LOC Rwy 36¹
RNAV (GPS) Rwy 18²
RNAV (GPS) Rwy 36²
RNAV (GPS)-A²

¹ILS, Category C, 800-2; Category D, 800-2¼;
Category E, 800-2½. LOC, Category D,
800-2¼, Category E, 800-2½.
²Category D, 800-2¼; Category E, 800-2½.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



ALTERNATE MINS

17257

M5

SE-2



**ALTERNATE MINS**

17257

M6



NAME ALTERNATE MINIMUMS
NEW BERN, NC
 COASTAL CAROLINA
 RGNL (EWN)..... **ILS or LOC Rwy 4¹**
 RNAV (GPS) Rwy 4²
 RNAV (GPS) Rwy 22
 VOR Rwy 22

NA when local weather not available.

¹ILS, LOC, Category D, 1100-3.

²Category D, 1100-3.

NEWBERRY, SC
 NEWBERRY COUNTY (EOE)..... **NDB Rwy 22**
 RNAV (GPS) Rwy 4
 RNAV (GPS) Rwy 22
 RNAV (GPS) Rwy 22

NA when local weather not available.

NORTH MYRTLE BEACH, SC
 GRAND STRAND
 (CRE) **ILS or LOC Rwy 23¹**
 RNAV (GPS) Rwy 5²
 RNAV (GPS) Rwy 23²
 VOR Rwy 5²
 VOR Rwy 23²

NA when local weather not available.

¹ILS, Category D, 700-2¹/₄. LOC, Category D, 800-2¹/₄.

²Category D, 800-2¹/₄.

NORTH WILKESBORO, NC
 WILKES
 COUNTY (UKF)..... **ILS Y or LOC Y Rwy 1**
 ILS Z or LOC Z Rwy 1
 RNAV (GPS) Rwy 1
 RNAV (GPS) Rwy 19

NA when local weather not available.

Category D, 1000-3.

OAK ISLAND, NC
 CAPE FEAR RGNL JETPORT/HOWIE
 FRANKLIN FIELD (SUT) **RNAV (GPS) Rwy 5**
 RNAV (GPS) Rwy 23

NA when local weather not available.

ORANGETOWN, SC
 ORANGETOWN
 MUNI (OGB)..... **RNAV (GPS) Rwy 5¹**
 RNAV (GPS) Rwy 17²
 RNAV (GPS) Rwy 23¹
 RNAV (GPS) Rwy 35¹

NA when local weather not available.

¹Category D, 800-2¹/₄.

²Category D, 800-2¹/₄.

NAME ALTERNATE MINIMUMS
OXFORD, NC
 HENDERSON-OXFORD (HNZ) **LOC Rwy 6**
 NDB Rwy 6
 RNAV (GPS) Rwy 6
 RNAV (GPS) Rwy 24

NA when local weather not available.

Category D, 800-2¹/₄.

PINEHURST/SOUTHERN PINES, NC
 MOORE
 COUNTY (SOP) **ILS Y or LOC Y Rwy 5¹**
 ILS Z or LOC Z Rwy 5
 RNAV (GPS) Rwy 5²
 RNAV (GPS) Rwy 23²

NA when local weather not available.

¹ILS, Category C, 700-2; Category D, 1000-3; LOC, Category D, 1000-3.

²Category D, 1000-3.

RALEIGH/DURHAM, NC
 RALEIGH-DURHAM
 INTL (RDU) **ILS or LOC Rwy 5L¹**
 ILS or LOC Rwy 5R¹
 ILS or LOC Rwy 23L²
 ILS or LOC Rwy 23R²
 VOR Rwy 32³

¹ILS, Category D, 700-2.

²ILS, Categories A,B, 800-2; Category C, 800-2¹/₄; Category D, 800-2¹/₂. LOC, Category C, 800-2¹/₄; Category D, 800-2¹/₂.

³Category C, 800-2¹/₄; Category D, 800-2¹/₂.

REIDSVILLE, NC
 ROCKINGHAM COUNTY NC
 SHILOH (SIF)..... **NDB Rwy 31**
 RNAV (GPS) Rwy 13
 RNAV (GPS) Rwy 31

NA when local weather not available.

ROANOKE RAPIDS, NC
 HALIFAX-NORTHAMPTON
 RGNL (IXA)..... **RNAV (GPS) Rwy 2**
 RNAV (GPS) Rwy 20
 VOR Rwy 2

Category D, 800-2¹/₄.

ROCK HILL, SC
 ROCK HILL/YORK CO/
 BRYANT FIELD (UZA) **RNAV (GPS) Rwy 2¹**
 RNAV (GPS) Rwy 20

NA when local weather not available.

¹Category D, 800-2¹/₄.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

**ALTERNATE MINS**

17257

M6

SE-2





ALTERNATE MINS

17257

M7



NAME ALTERNATE MINIMUMS
ROCKINGHAM, NC
 RICHMOND
 COUNTY (RCZ) RNAV (GPS) Rwy 32
 NA when local weather not available.

ROCKY MOUNT, NC
 ROCKY MOUNT-
 WILSON RGNL (RWI) RNAV (GPS) Rwy 4
 RNAV (GPS) Rwy 22
 VOR/DME Rwy 22
 NA when local weather not available.

ROXBORO, NC
 PERSON
 COUNTY (TDF) RNAV (GPS) Rwy 6
 RNAV (GPS) Rwy 24
 NA when local weather not available.

RUTHERFORDTON, NC
 RUTHERFORD CO/MARCHMAN
 FIELD (FQD) RNAV (GPS) Rwy 1
 NA when local weather not available.
 Category D, 800-2½.

SANFORD, NC
 RALEIGH EXECUTIVE JETPORT AT SANFORD
 -LEE COUNTY (TTA) RNAV (GPS) Rwy 3
 RNAV (GPS) Rwy 21
 NA when local weather not available.
 Category D, 800-2¼.

SALISBURY, NC
 MID-CAROLINA
 RGNL (RUQ) RNAV (GPS) Rwy 2
 RNAV (GPS) Rwy 20
 NA when local weather not available.

SHELBY, NC
 SHELBY-CLEVELAND
 COUNTY RGNL (EHO) NDB Rwy 23¹
 RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 NA when local weather not available.
¹Category C, 800-2¼; Category D, 800-2½.

SILER CITY, NC
 SILER CITY
 MUNI (SCR) RNAV (GPS) Rwy 4
 RNAV (GPS) Rwy 22
 VOR-A¹
 NA when local weather not available.
¹Category C, 800-2¼.

NAME ALTERNATE MINIMUMS
SMITHFIELD, NC
 JOHNSTON
 RGNL (JNX) RNAV (GPS) Rwy 3
 RNAV (GPS) Rwy 21
 NA when local weather not available.
 Category C, 800-2¼; Category D, 1000-3.

SPARTANBURG, SC
 SPARTANBURG DOWNTOWN
 MEMORIAL (SPA) ILS or LOC Rwy 5
 RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 23
 NA when local weather not available.

STATESVILLE, NC
 STATESVILLE
 RGNL (SVH) ILS or LOC/DME Y Rwy 28¹
 ILS or LOC/DME Z Rwy 28¹
 RNAV (GPS) Rwy 10
 RNAV (GPS) Rwy 28
 VOR/DME Rwy 10
 NA when local weather not available.
¹NA when FBO closed.

SUMMERVILLE, SC
 SUMMERVILLE (DYB) RNAV (GPS) Rwy 6
 RNAV (GPS) Rwy 24
 NA when local weather not available.
 Categories A, B, 900-2; Category C, 900-2¼.

SUMTER, SC
 SUMTER (SMS) ILS or LOC/DME Rwy 23
 RNAV (GPS) Rwy 5¹
 RNAV (GPS) Y Rwy 23
 RNAV (GPS) Z Rwy 23
 NA when local weather not available.
¹Category C, 800-2¼; Category D, 800-2½.

WADESBORO, NC
 ANSON COUNTY-JEFF CLOUD
 FIELD (AFP) ILS or LOC Rwy 34¹
 RNAV (GPS) Rwy 16²
 RNAV (GPS) Rwy 34²
 NA when local weather not available.
¹ILS, Category C, 700-1¾; Category D, 700-2¼. LOC, Category D, 800-2¼.
²Category D, 800-2¼.

WALTERBORO, SC
 LOWCOUNTRY
 RGNL (RBW) RNAV (GPS) Rwy 5
 RNAV (GPS) Rwy 17
 RNAV (GPS) Rwy 23
 RNAV (GPS) Rwy 35
 NA when local weather not available.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



ALTERNATE MINS

17257

M7

SE-2





ALTERNATE MINS

M8



17257

NAME	ALTERNATE MINIMUMS	NAME	ALTERNATE MINIMUMS
WASHINGTON, NC			
WASHINGTON-			
WARREN (OCW)	RNAV (GPS) Rwy 5		
	RNAV (GPS) Rwy 17		
	RNAV (GPS) Rwy 23		
	RNAV (GPS) Rwy 35		
	VOR/DME Rwy 5¹		

NA when local weather not available.

¹Categories C, D, 800-2½.

WHITEVILLE, NC

COLUMBUS COUNTY

MUNI (CPC) **NDB Rwy 6**

RNAV (GPS) Rwy 6

RNAV (GPS) Rwy 24¹

NA when local weather not available.

¹Category D, 800-2¼.

WILMINGTON, NC

WILMINGTON

INTL (ILM) **ILS Y or LOC Rwy 6²**

ILS Y or LOC Rwy 24²

ILS Y or LOC Rwy 35¹²

RADAR-1¹³

RNAV (GPS) Rwy 6³

RNAV (GPS) Rwy 17³

RNAV (GPS) Rwy 24³

RNAV (GPS) Rwy 35³

TACAN-A³

¹NA when control tower closed.

²ILS, Category C, 700-2; Category D, 900-3;

LOC, Category D, 900-3.

³Category D, 900-3.

WINNSBORO, SC

FAIRFIELD

COUNTY (FDW) **NDB Rwy 4**

RNAV (GPS) Rwy 4

RNAV (GPS) Rwy 22

NA when local weather not available.

WINSTON-SALEM, NC

SMITH

REYNOLDS (INT) **ILS or LOC Rwy 33¹²**

RNAV (GPS) Rwy 15³⁴

RNAV (GPS) Rwy 33³⁵

VOR Rwy 15⁵

¹NA when control tower closed.

²ILS, Categories B, C, 700-2; Category D, 800-2½. LOC, Category D, 800-2½.

³NA when local weather not available.

⁴Category D, 800-2¼.

⁵Category D, 800-2½.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



ALTERNATE MINS

M8

SE-2



17257

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

INSTRUMENT APPROACH PROCEDURE CHARTS



IFR TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

Civil Airports and Selected Military Airports

ALL USERS: Airports that have Departure Procedures (DPs) designed specifically to assist pilots in avoiding obstacles during the climb to the minimum enroute altitude, and/or airports that have civil IFR takeoff minimums other than standard, are listed below. Takeoff Minimums and Departure Procedures apply to all runways unless otherwise specified. Altitudes, unless otherwise indicated, are minimum altitudes in MSL.

DPs specifically designed for obstacle avoidance are referred to as Obstacle Departure Procedures (ODPs) and are textually described below, or published separately as a graphic procedure. If the ODP is published as a graphic procedure, its name will be listed below, and it can be found in either this volume (civil), or the applicable military volume, as appropriate. Users will recognize graphic obstacle DPs by the term "(OBSTACLE)" included in the procedure title; e.g., TETON TWO (OBSTACLE). If not specifically assigned an ODP, SID, or radar vector as part of an IFR clearance, an ODP may be required to be flown for obstacle clearance, even though not specifically stated in the IFR clearance. When doing so in this manner, ATC should be informed when the ODP being used contains a specified route to be flown, restrictions before turning, and/or altitude restrictions.

Some ODPs, which are established solely for obstacle avoidance, require a climb in visual conditions to cross the airport, a fix, or a NAVAID in a specified direction, at or above a specified altitude. These procedures are called Visual Climb Over Airport (VCOA). To ensure safe and efficient operations, the pilot must verbally request approval from ATC to fly the VCOA when requesting their IFR clearance.

At some locations where an ODP has been established, a diverse vector area (DVA) may be created to allow radar vectors to be used in lieu of an ODP. DVA information will state that headings will be as assigned by ATC and climb gradients, when applicable, will be published immediately following the specified departure procedure.

Graphic DPs designed by ATC to standardize traffic flows, ensure aircraft separation and enhance capacity are referred to as "Standard Instrument Departures (SIDs)". SIDs also provide obstacle clearance and are published under the appropriate airport section. An instrument must be received prior to flying a SID.

CIVIL USERS NOTE: Title 14 Code of Federal Regulations Part 91 prescribes standard takeoff rules and establishes takeoff minimums for certain operators as follows: (1) For aircraft, other than helicopters, having two engines or less – one statute mile visibility. (2) For aircraft having more than two engines – one-half statute mile visibility. (3) For helicopters – one-half statute mile visibility. These standard minima apply in the absence of any different minima listed below.

MILITARY USERS NOTE: Civil (nonstandard) takeoff minima are published below. For military takeoff minima, refer to appropriate service directives.

NAME TAKEOFF MINIMUMS

NAME TAKEOFF MINIMUMS

AHOSKIE, NC**TRI-COUNTY (ASJ)**

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 11 125 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 1**, trees beginning at DER, 219' left of centerline, up to 100' AGL/169' MSL. Vehicles on road beginning 206' from DER, 443' left of centerline, up to 10' AGL/79' MSL. Trees beginning 457' from DER, 461' right of centerline, up to 100' AGL/169' MSL. Power lines beginning 5130' from DER, 1827' right of centerline, up to 150' AGL/219' MSL. **Rwy 19**, vehicles on road 234' from DER, 502' right of centerline, up to 10' AGL/79' MSL. Vehicles on road beginning 244' from DER, left and right of centerline, up to 15' AGL/84' MSL. Trees beginning 717' from DER, 626' right of centerline, up to 100' AGL/169' MSL. Trees beginning 277' from DER, 244' left of centerline, up to 100' AGL/169' MSL.

AIKEN, SC**AIKEN MUNI (AIK)**

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDPT 1 08045 (FAA)

TAKEOFF MINIMUMS: **Rwy 1**, 200-1/4 or std. w/ min. climb of 220' per NM to 800, or alternatively, with std. takeoff min. and a normal 200' NM climb gradient, takeoff must occur no later than 1400' prior to DER.

DEPARTURE PROCEDURE: **Rwy 19**, climb heading 186° to 1100 before turning west.

TAKEOFF OBSTACLE NOTES: **Rwy 1**, terrain 74' from DER, 9' left of centerline, 496' MSL. Numerous trees beginning 169' from DER, 35' left of centerline, up to 100' AGL/659' MSL. Tree 6,023' from DER, 1,609' left of centerline, up to 100' AGL/649' MSL. Terrain beginning 75' from DER, 246' right of centerline up to 496' MSL. Numerous trees beginning 1322' from DER, 241' right of centerline, up to 100' AGL/609' MSL. **Rwy 7**, terrain beginning 51' from DER, 207' right of centerline up to 499' MSL. Numerous trees beginning 1230' from DER, 550' right of centerline, up to 100' AGL/609' MSL. Numerous trees beginning 1601' from DER, 731' left of centerline, up to 56' AGL/563' MSL. **Rwy 19**, numerous trees beginning at DER, 110' right of centerline, up to 100' AGL/629' MSL. numerous trees beginning 6' from DER, 82' left of centerline, up to 100' AGL/639' MSL. **Rwy 25**, tree 1244' from DER, 766' right of centerline, 73' AGL/572' MSL. Tree 1506' from DER, 661' left of centerline, 72' AGL/561' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

ALBEMARLE, NC

STANLY COUNTY (VUJ)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 11321 (FAA)

TAKEOFF MINIMUMS: **Rwys 4L, 22R**, NA - VFR
runway. **Rwy 4R**, 300-1½ or std. w/min. climb of 276'
per NM to 1000.

TAKEOFF OBSTACLE NOTES: **Rwy 4R**, tree 4312'
from DER, 374' right of centerline, 78' AGL/692' MSL.
Tree 1.2 NM from DER, 2063' left of centerline, 98'
AGL/837' MSL. **Rwy 22L**, trees beginning 190' from
DER, 142' right of centerline, up to 82' AGL/682' MSL.
Railroad 438' from DER, 403' right of centerline, 23'
AGL/620' MSL.

ALLENDALE, SC

ALLENDALE COUNTY (AQX)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 13290 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 17**, trees
beginning 11' from DER, 366' right of centerline, up to
100' AGL/222' MSL. Vehicles on roadway beginning
293' from DER, 558' left of centerline, up to 15'
AGL/164' MSL. Trees 342' from DER, 577' left of
centerline, up to 100' AGL/214' MSL. Trees beginning
1962' from DER, 603' left of centerline, up to 100'
AGL/246' MSL. **Rwy 35**, trees beginning 38' from DER,
306' right of centerline, up to 100' AGL/269' MSL.
Trees beginning 95' from DER, 324' left of centerline,
up to 100' AGL/289' MSL.

ANDERSON, SC

ANDERSON RGNL (AND)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 07018 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, multiple trees
beginning 1282' from DER, 172' right of centerline, up
to 93' AGL/879' MSL. Multiple trees beginning 85' from
DER, 299' left of centerline, up to 89' AGL/878' MSL.
Rwy 17, multiple trees beginning 1017' from DER,
25' right of centerline, up to 73' AGL/800' MSL.
Multiple trees beginning 3' from DER, 47' left of
centerline, up to 77' AGL/820' MSL. **Rwy 23**,
transmission line tower and multiple trees beginning
1186' from DER, 552' left of centerline, up to 100'
AGL/890' MSL. **Rwy 35**, multiple trees beginning 131'
from DER, 279' right of centerline, up to 87' AGL/854'
MSL. Ceilometer and tree beginning 257' from DER,
319' left of centerline, up to 73' AGL/820' MSL.

ANDREWS, NC

WESTERN CAROLINA RGNL (RHP)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1A 10014 (FAA)

TAKEOFF MINIMUMS: **Rwys 8, 26**, max. 180 KIAS
3400-2, max. 210 KIAS 3400-2½, max. 250 KIAS 3400
-3.

DEPARTURE PROCEDURE: **Rwys 8, 26**, procedure
NA at night. Remain within 3 NM of Western Carolina
RGNL while climbing in visual conditions to cross
airport westbound at or above 4900. Then climb to
7000 via heading 251° and HARRIS (HRS) VORTAC
R-356 to HRS VORTAC before proceeding on course.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

ANDREWS, SC

ROBERT F. SWINE (PHH)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 02276 (FAA)

TAKEOFF MINIMUMS: **Rwy 18**, 300-1. **Rwy 36**, 400-1.
DEPARTURE PROCEDURE: **Rwys 18, 36**, climb runway
heading to 500 before turning left.

TAKEOFF OBSTACLE NOTES: **Rwy 18**, tower 165' from
DER, 500' right of centerline, 118' AGL/145' MSL. Tree
630' from DER, 350' left of centerline, 87' AGL/114' MSL.
Water tank 340' from DER, 1040' right of centerline, 129'
AGL/156' MSL. **Rwy 36**, tree 60' from DER, 500' left of
centerline, 67' AGL/85' MSL. Tree 10' from DER, 210'
right of centerline, 55' AGL/73' MSL. Tree 10' from DER,
190' left of centerline, 32' AGL/50' MSL. Tree 720' from
DER, 265' right of centerline, 34' AGL/61' MSL.

ASHEBORO, NC

ASHEBORO RGNL (HBI)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 02332 (FAA)

TAKEOFF MINIMUMS: **Rwy 3**, std. with a min. climb of
230' per NM to 1200. **Rwy 21**, 400-2 or std. with a min.
climb of 340' per NM to 1200.

DEPARTURE PROCEDURE: **Rwy 21**, climb runway
heading to 1500 before turning southeast.

ASHEVILLE, NC

ASHEVILLE RGNL (AVL)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 15344 (FAA)

TAKEOFF MINIMUMS: **Rwy 17**, std. w/ min. climb of 250'
per NM to 4600 or 3600-3 for climb in visual conditions.

Rwy 35, std. w/ min. climb of 410' per NM to 5700 or
3600-3 for climb in visual conditions.

DEPARTURE PROCEDURE: **Rwy 17**, climb heading 167°
to 4600 before proceeding on course. **Rwy 35**, climb
heading 347° to 5700 before proceeding on course.

VCOA: **Rwy 17**, obtain ATC approval for climb in visual
conditions when requesting IFR clearance. Climb in
visual conditions to cross Asheville Rgnl airport at or
above 5600 before proceeding on course. Note: VCOA
NA at night. **Rwy 35**, obtain ATC approval for climb in
visual conditions when requesting IFR clearance. For
climb in visual conditions to cross Asheville Rgnl airport
at or above 5600 before proceeding on course. Note:
VCOA NA at night.

TAKEOFF OBSTACLE NOTES: **Rwy 17**, trees beginning
79' from DER, 452' right of centerline, up to 73'
AGL/2144' MSL. **Rwy 35**, vehicle on road 44' from DER,
202' left of centerline, 15' AGL/2166' MSL. Trees
beginning 65' from DER, 245' left of centerline, up to 92'
AGL/2232' MSL. Trees beginning 701' from DER, 16' left
of centerline, up to 65' AGL/2197' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017


TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND


DIVERSE VECTOR AREA (RADAR VECTORS)

17229

BAMBERG, SC

BAMBERG COUNTY (99N)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

ORIG 11013 (FAA)

TAKEOFF MINIMUMS: **Rwy 5**, 400-2½ or std. w/ min. climb of 259' per NM to 800.TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning at DER, 500' left/right of centerline, up to 100' AGL/329' MSL. Power lines 2,527' from DER, crossing centerline, up to 100' AGL/319' MSL. Tower 2 NM from DER, 2738' right of centerline, 380' AGL/627' MSL.**Rwy 23**, trees beginning at DER, 500' left of centerline, up to 100' AGL/319' MSL.**BARNWELL, SC**

BARNWELL RGNL (BNL)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 2 07214 (FAA)

TAKEOFF MINIMUMS: **Rwy 17**, 300-2½ or std. w/ min. climb of 241' per NM to 800.DEPARTURE PROCEDURE: **Rwy 17**, climb heading 165° to 1100 before turning. **Rwy 23**, climb heading 230° to 1100 before turning south.TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 1959' from DER, 506' right of centerline, up to 100' AGL/329' MSL. Trees beginning 2458' from DER, 440' left of centerline, up to 100' AGL/359' MSL. **Rwy 17**, trees beginning 3225' from DER, 1092' right of centerline, up to 100' AGL/ 339' MSL. Tower 1.9 NM from DER, 3064' left of centerline, 366' AGL/544' MSL. **Rwy 23**, trees beginning 717' from DER, 237' right of centerline, up to 100' AGL/339' MSL. Trees beginning 971' from DER, 254' left of centerline, 100' AGL/349' MSL. Tree 2933' from DER, 559' left of centerline, 100' AGL/319' MSL. **Rwy 35**, trees beginning 948' from DER, 570' left of centerline, up to 100' AGL/349' MSL. Trees beginning 2805' from DER, 440' right of centerline, up to 100' AGL/359' MSL.**BEAUFORT, NC**

MICHAEL J. SMITH FIELD (MRH)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 4 13122 (FAA)

TAKEOFF MINIMUMS: **Rwy 21**, 300-1 or std. w/ min. climb of 740' per NM to 300.TAKEOFF OBSTACLE NOTES: **Rwy 3**, tree 41' from DER, 379' left of centerline, 58' AGL/64' MSL. Trees beginning 1030' from DER, 351' right of centerline, up to 54' AGL/62' MSL. Trees beginning 1873' from DER, 21' left of centerline, up to 100' AGL/109' MSL. Tree 2070' from DER, 106' right of centerline, 80' AGL/86' MSL. Tree 3039' from DER, 613' right of centerline, 100' AGL/114' MSL. **Rwy 8**, trees beginning 447' from DER, 140' left of centerline, up to 31' AGL/51' MSL. Tree 3609' from DER, 577' left of centerline, 100' AGL/104' MSL.**Rwy 14**, trees beginning 148' from DER, left and right of centerline, up to 100' AGL/114' MSL. **Rwy 21**, vehicles on roadway 262' from DER, left and right of centerline, up to 15' AGL/24' MSL. Trees beginning 475' from DER, 132' right of centerline, up to 100' AGL/104' MSL. Boats beginning 506' from DER, left and right of centerline, up to 77' AGL/77' MSL. Tower 2566' from DER, 925' left of centerline, 162' AGL/172' MSL. **Rwy 26**, trees beginning 52' from DER, 308' left of centerline, up to 43' AGL/49' MSL. Building and trees beginning 131' from DER, 417' right of centerline, 18' AGL/24' MSL. Boats beginning 383' from DER, left and right of centerline, up to 77' AGL/77' MSL. **Rwy 32**, trees beginning 30' from DER, 182' left of centerline, up to 100' AGL/104' MSL. Trees beginning 30' from DER, 419' right of centerline, up to 100' AGL/104' MSL. Boats beginning 452' from DER, left and right of centerline, up to 77' AGL/77' MSL.**BEAUFORT, SC**

BEAUFORT COUNTY (ARW)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 1 03191 (FAA)

DEPARTURE PROCEDURE: **Rwy 7**, climb runway heading to 1700 before turning right. **Rwy 25**, climb runway heading to 300 before turning right.TAKEOFF OBSTACLE NOTES: **Rwy 25**, tree 1100' from DER, 70' left of centerline, 40' AGL/50' MSL. Power line 1000' from DER, on centerline, 30' AGL/ 35' MSL.**BENNETTSVILLE, SC**

MARLBORO COUNTY JETPORT-H E

AVENT FIELD (BBP)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 1 10210 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 7**, pole 97' from DER, 379' right of centerline, 35' AGL/181' MSL. Trees beginning 1415' from DER, 412' left of centerline, up to 86' AGL/232' MSL. Trees beginning 2495' from DER, 256' right of centerline, up to 89' AGL/235' MSL. **Rwy 25**, tree 77' from DER, 148' right of centerline, 18' AGL/156' MSL. Trees beginning 2681' from DER, 382' right of centerline, up to 89' AGL/227' MSL.

17229


TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND


DIVERSE VECTOR AREA (RADAR VECTORS)



TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)



BOGUE MCALF (KNJM), SWANSBORO, NC

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1, 17089

TAKEOFF OBSTACLE NOTES: **Rwy 5**, pylon 4809' from DER, 1783' left of centerline, 89' AGL/120' MSL. Terrain 0' from DER, 500' right of centerline, 29' MSL. Terrain 0' from DER, 500' left of centerline, 20' MSL. **Rwy 23**, terrain 95' from DER, 435' left of centerline, 30' MSL. Terrain 0' from DER, 500' left of centerline, 33' MSL. Terrain 0' from DER, 25' right of centerline, 18' MSL. Terrain 129' from DER, 530' right of centerline, 26' MSL.

CHAPEL HILL, NC

HORACE WILLIAMS (IGX)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 3 06215 (FAA)

DEPARTURE PROCEDURE: **Rwy 9**, climb heading 090° to 1400 before turning southwest. **Rwy 27**, climb heading 270° to 2400 before turning south.
TAKEOFF OBSTACLE NOTES: **Rwy 9**, trees 1084' from DER, 250' left of centerline, 82' AGL/551' MSL. Trees 785' from DER, 401' right of centerline, 56' AGL/520' MSL. **Rwy 27**, trees 200' from DER, 240' left of centerline, 43' AGL/542' MSL.

BURLINGTON, NC

BURLINGTON-ALAMANCE RGNL (BUY)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 14037 (FAA)

TAKEOFF MINIMUMS: **Rwy 6**, 300-3 or std. w/ min. climb of 285' per NM to 900.
DEPARTURE PROCEDURE: **Rwy 6**, climb heading 060° to 1500 before turning. **Rwy 24**, climb heading 240° to 1500 before turning.
TAKEOFF OBSTACLE NOTES: **Rwy 6**, trees, antenna, transmission towers, communications towers, tank and poles left and right of centerline beginning 158' from DER, 482' right of centerline up to 163' AGL/785' MSL. **Rwy 24**, trees, pole and runway 6 REILs left and right of centerline beginning 10' from DER, 125' left and right of centerline up to 100' AGL/676' MSL.

CAMDEN, SC

WOODWARD FIELD (CDN)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 07298 (FAA)

TAKEOFF MINIMUMS: **Rwy 6**, 200-1¼ or std. w/ min. climb of 362' per NM to 700.
TAKEOFF OBSTACLE NOTES: **Rwy 6**, light 184' from DER, 500' right of centerline, 27' AGL/316' MSL. Trees beginning 867' from DER, 113' right of centerline, up to 83' AGL/373' MSL. Trees beginning 736' from DER, 256' left of centerline, up to 100' AGL/419' MSL. Water tank 5407' from DER, 1852' left of centerline, 168' AGL/487' MSL. **Rwy 14**, trees and terrain beginning 90' from DER, 68' left of centerline, up to 100' AGL/409' MSL. Trees and terrain beginning 159' from DER, 148' right of centerline, up to 100' AGL/399' MSL. **Rwy 24**, trees beginning 137' from DER, 413' right of centerline, up to 100' AGL/338' MSL. Trees beginning 234' from DER, 389' left of centerline, up to 100' AGL/347' MSL. **Rwy 32**, trees beginning 3059' from DER, 455' right of centerline, up to 100' AGL/449' MSL. Tree 5066' from DER, 858' left of centerline, 100' AGL/429' MSL.

CHARLESTON, SC

CHARLESTON AFB/INTL (CHS)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 7 11237 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 3**, electrical equipment, towers, and trees beginning 98' from DER, 409' right of centerline, up to 104' AGL/ 136' MSL. Tree 2653' from DER, 993' left of centerline, 100' AGL/ 139' MSL. **Rwy 15**, trees beginning 1297' from DER, 772' left of centerline, up to 100' AGL/ 119' MSL. **Rwy 33**, trees beginning 2190' from DER, 1002' right of centerline, up to 100' AGL/ 139' MSL. Trees beginning 3061' from DER, 1284' left of centerline, up to 100' AGL/ 144' MSL.

CHARLESTON EXECUTIVE (JZI)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1A 16007 (FAA)

DEPARTURE PROCEDURE: **Rwy 22**, climb heading 217° to 600 before turning right.
TAKEOFF OBSTACLE NOTES: **Rwy 4**, trees beginning 2473' from DER, 530' left of centerline, up to 75' AGL/85' MSL. **Rwy 9**, antenna 110' from DER, 444' left of centerline, 39' AGL/47' MSL. **Rwy 22**, trees 502' from DER, 181' right of centerline, up to 100' AGL/109' MSL. Trees beginning 2183' from DER, left to right of centerline up to 100' AGL/109' MSL. **Rwy 27**, trees beginning 779' from DER, 84' left of centerline, up to 77' AGL/96' MSL. Pole 1011' from DER, 585' left of centerline, 42' AGL/61' MSL. Trees beginning 90' from DER, 273' right of centerline, up to 60' AGL/78' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

CHARLOTTE, NC

CHARLOTTE/DOUGLAS INTL (CLT)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 7 16203 (FAA)

TAKEOFF MINIMUMS: **Rwy 18C**, 300-1¼ or std. w/min. climb of 220' per NM to 900, or alternatively with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1500' prior to DER.

DEPARTURE PROCEDURE: **Rwy 5**, climb heading 055° to 1700 before turning right. **Rwy 36C**, climb heading 003° to 1400 before turning left. **Rwy 36L**, climb heading 023° to 1800 before turning left.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, tree 810' from DER, 677' right of centerline, 768' MSL. Tree 1031' from DER, 665' left of centerline, 773' MSL. Tree 1050' from DER, 755' left of centerline, 787' MSL. Tree 1894' from DER, 854' left of centerline, 799' MSL. Trees beginning 2088' from DER, 877' left of centerline, up to 821' MSL. Trees beginning 2437' from DER, 971' left of centerline, up to 822' MSL. Tree 2582' from DER, 1056' left of centerline, 843' MSL. Trees beginning 2608' from DER, 543' left of centerline, up to 848' MSL. Tree 3977' from DER, 480' left of centerline, 856' MSL. **Rwy 18C**, airfield lt 11' from DER, 84' left of centerline, 4' AGL/695' MSL. Tree 555' from DER, 564' left of centerline, 711' MSL. Tree 1059' from DER, 762' right of centerline, 729' MSL. Trees beginning 1183' from DER, 608' left of centerline, up to 746' MSL. Trees beginning 1478' from DER, 276' left of centerline, up to 757' MSL. Tree 2035' from DER, 1025' left of centerline, 764' MSL. Trees beginning 2058' from DER, 182' right of centerline, up to 771' MSL. Tree 2723' from DER, 971' left of centerline, 773' MSL. Trees beginning 3245' from DER, 793' right of centerline, up to 792' MSL. Tree 4249' from DER, 1039' right of centerline, 805' MSL. Tree 5354' from DER, 1810' right of centerline, 831' MSL. Trees beginning 5551' from DER, 1412' right of centerline, up to 120' AGL/848' MSL. **Rwy 18L**, airfield lt 10' from DER, on centerline, 3' AGL/726' MSL. Pole 981' from DER, 708' left of centerline, 64' AGL/763' MSL. Twr and tree beginning 981' from DER, 689' right of centerline, up to 765' MSL. Tree 1235' from DER, 795' right of centerline, 767' MSL. Trees beginning 1457' from DER, 703' right of centerline, up to 777' MSL. Tree 2248' from DER, 815' right of centerline, 783' MSL. Tower 4408' from DER, 1505' left of centerline, 160' AGL/849' MSL. **Rwy 18R**, airfield lt 10' from DER, 4' left of centerline, 3' AGL/746' MSL. Grd 145' from DER, 522' left of centerline, 748' MSL. **Rwy 23**, MALS R 1' from DER, on centerline, 706' MSL. Control box 1' from DER, 136' right of centerline, 4' AGL/708' MSL. Tree 1270' from DER, 772' right of centerline, 742' MSL. Tree 1310' from DER, 771' right of centerline, 753' MSL. Tree 1477' from DER, 702' right of centerline, 757' MSL. Trees beginning 1573' from DER, 654' right of centerline, up to 758' MSL. Trees beginning 1728' from DER, 541' right of centerline, up to 762' MSL. Trees beginning 1814' from DER, 597' right of centerline, up to 775' MSL. Tree 1844' from DER, 805' right of centerline, 776' MSL. Trees beginning 1944' from DER, 697' right of centerline, up to 792' MSL. Trees beginning 2242' from DER, 361' right of centerline, up to 811' MSL.

CHARLOTTE, NC (CON'T)

CHARLOTTE/DOUGLAS INTL (CLT) (CON'T)

Rwy 36C, airfield lt 4' from DER, 11' left of centerline, 1' AGL/743' MSL. Trees beginning 1246' from DER, 598' right of centerline, up to 822' MSL. Trees beginning 1937' from DER, 446' right of centerline, up to 823' MSL. Trees beginning 2045' from DER, 237' right of centerline, up to 827' MSL. **Rwy 36L**, airfield lt 9' from DER, 3' left of centerline, 2' AGL/745' MSL. Tree 1355' from DER, 544' left of centerline, 786' MSL. **Rwy 36R**, aprt sign 19' from DER, 289' right of centerline, 6' AGL/747' MSL. Trees beginning 470' from DER, 474' right of centerline, up to 767' MSL. Tree and railroad, beginning 640' from DER, 93' right of centerline, up to 775' MSL. Lt pole and tree beginning 837' from DER, 500' right of centerline, up to 777' MSL. Tree 943' from DER, 650' left of centerline, 771' MSL. Pole 1004' from DER, 739' left of centerline, 774' MSL. Trees beginning 1058' from DER, 346' right of centerline, up to 779' MSL. Pole 1191' from DER, 769' left of centerline, 778' MSL. Tree 1279' from DER, 625' right of centerline, 780' MSL. Tree 1295' from DER, 585' left of centerline, 782' MSL. Tree 1396' from DER, 646' right of centerline, 784' MSL. Trees beginning 1475' from DER, 1' left of centerline, up to 805' MSL. Tree 1612' from DER, 732' right of centerline, 787' MSL. Tree and pole beginning 1652' from DER, 718' right of centerline, up to 809' MSL. Trees beginning 1725' from DER, 557' right of centerline, up to 816' MSL. Trees beginning 1874' from DER, on centerline, up to 820' MSL. Tree 2053' from DER, 90' left of centerline, 59' AGL/807' MSL. Trees beginning 2070' from DER, 41' left of centerline, up to 72' AGL/815' MSL. Trees beginning 2132' from DER, 324' left of centerline, up to 823' MSL. Tree 2457' from DER, 919' left of centerline, 830' MSL. Tower 3685' from DER, 1160' right of centerline, 70' AGL/844' MSL. Tree 3737' from DER, 392' left of centerline, 91' AGL/843' MSL. Tree 3756' from DER, 530' right of centerline, 846' MSL. Trees beginning 3759' from DER, 433' left of centerline, up to 851' MSL. Trees beginning 3774' from DER, 578' right of centerline, up to 852' MSL. Trees beginning 3803' from DER, 171' left of centerline, up to 863' MSL.

CHERAW, SC

CHERAW MUNI/LYNCH BELLINGER FIELD
(CQW)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 07074 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 8**, multiple trees 465' from DER, 176' right of centerline, up to 100' AGL/279' MSL. Power lines 845' from DER, 501' left of centerline, 65' AGL/243' MSL. Multiple trees 2407' from DER, 11' left of centerline, up to 100' AGL/279' MSL. **Rwy 26**, trees 1089' from DER, 213' left of centerline, up to 100' AGL/389' MSL. Trees 1467' from DER, 63' right of centerline, up to 100' AGL/379' MSL. Power lines 2066' from DER, 186' right of centerline, 65' AGL/243' MSL.

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

CHERRY POINT MCAS (CUNNINGHAM FLD) (KNKT)

CHERRY POINT, NC

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
16091

Rwy 5R, 14L, 23R, 32L: Diverse departures not authorized.

TAKEOFF OBSTACLE NOTES: Rwy 14R: Pylon 3822' from DER, 1424' right of centerline, 69' MSL. Pylon 3980' from DER, 1472' right of centerline, 69' MSL.

CHESTER, SC

CHESTER CATAWBA RGNL (DCM)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 09015 (FAA)

TAKEOFF OBSTACLE NOTES: Rwy 5, trees beginning 383' from DER, 180' left of centerline up to 100' AGL/719' MSL. **Rwy 17,** trees beginning 54' from DER, 289' left of centerline up to 100' AGL/739' MSL. Trees beginning 164' from DER, 291' right of centerline up to 100' AGL/739' MSL. **Rwy 23,** trees beginning 163' from DER, 379' right of centerline up to 100' AGL/729' MSL. Trees beginning 3229' from DER, 726' left of centerline up to 100' AGL/779' MSL. **Rwy 35,** vehicle on road 761' from DER, 684' left of centerline up to 15' AGL/734' MSL. Trees beginning 321' from DER, 684' right of centerline up to 100' AGL/761' MSL.

CLEMSON, SC

OCONEE COUNTY RGNL (CEU)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 3 11321 (FAA)

DEPARTURE PROCEDURE: Rwy 25, climb heading 253° to 1900 before turning right.

TAKEOFF OBSTACLE NOTES: Rwy 7, trees beginning 8' from DER, 310' left of centerline, up to 35' AGL/909' MSL. Trees beginning 87' from DER, 93' right of centerline, up to 100' AGL/979' MSL. **Rwy 25,** trees beginning 109' from DER, 6' right of centerline, up to 100' AGL/979' MSL. Trees beginning 123' from DER, 8' left of centerline, up to 83' AGL/971' MSL. Multiple poles beginning 457' from DER, left and right of centerline, up to 48' AGL/936' MSL.

CLINTON, NC

CLINTON-SAMPSON COUNTY (CTZ)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 11125 (FAA)

TAKEOFF OBSTACLE NOTES: Rwy 6, trees 10' from DER, 393' right of centerline, up to 116' AGL/245' MSL. Trees 1306' from DER, 9' left of centerline, up to 100' AGL/269' MSL. **Rwy 24,** trees 14' from DER, 3' right of centerline, up to 99' AGL/188' MSL. Tree 1718' from DER, 891' left of centerline, 100' AGL/219' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

COLUMBIA, SC

COLUMBIA METROPOLITAN (CAE)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 1 09239 (FAA)

TAKEOFF OBSTACLE NOTES: Rwy 5, trees beginning 127' from DER, 128' left of centerline, up to 97' AGL/286' MSL. Trees beginning 420' from DER, 21' right of centerline, up to 74' AGL/283' MSL. **Rwy 11,** trees beginning 1896' from DER, 621' left of centerline, up to 48' AGL/277' MSL. Light pole and trees beginning 1043' from DER, 723' right of centerline, up to 69' AGL/268' MSL. **Rwy 23,** trees 3573' from DER, 1191' right of centerline, up to 60' AGL/329' MSL. **Rwy 29,** trees beginning 567' from DER, 535' left of centerline, up to 87' AGL/286' MSL. Trees beginning 1045' from DER, 526' right of centerline, up to 63' AGL/332' MSL.

JIM HAMILTON L B OWENS (CUB)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 3 09323 (FAA)

TAKEOFF MINIMUMS: Rwy 31, 600-2½ or std. with min. climb of 345' per NM to 1000.

DEPARTURE PROCEDURE: Rwy 31, climb heading 311° to 1500 before turning Northbound.

TAKEOFF OBSTACLE NOTES: Rwy 13, trains beginning at DER, 138' right of centerline, up to 23' AGL/202' MSL. Trees beginning 3' from DER, 88' right of centerline, up to 106' AGL/255' MSL. Trees beginning 131' from DER, 84' left of centerline, up to 97' AGL/256' MSL. **Rwy 31,** trains beginning at DER, 437' left of centerline, up to 23' AGL/222' MSL. Buildings beginning 632' from DER, 260' right of centerline, up to 372' AGL/681' MSL. Buildings beginning 1050' from DER, 20' left of centerline, up to 50' AGL/252' MSL. Tower 2.1 NM from DER, 3510' right of centerline, 422' AGL/747' MSL.

CONCORD, NC

CONCORD RGNL (JQF)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 3 10070 (FAA)

TAKEOFF MINIMUMS: Rwy 20, 300-1¼ or std. w/ min. climb of 204' per NM to 1000, or alternatively, with standard takeoff minimums and a normal 200'/NM climb gradient, takeoff must occur no later than 1200' prior to DER.

DEPARTURE PROCEDURE: Rwy 2, climb heading 016° to 2200 before proceeding on course. **Rwy 20,** climbing right turn heading 290° to intercept CLT VOR/DME R-039 outbound to 2100 before proceeding on course.

TAKEOFF OBSTACLE NOTES: Rwy 2, poles and trees beginning 2624' from DER, 688' left of centerline, up to 45' AGL/784' MSL. Trees beginning 2107' from DER, 787' right of centerline, up to 24' AGL/783' MSL. **Rwy 20,** street lights beginning 3047' from DER, 1.96' right of centerline, up to 105' AGL/744' MSL. Trees 1.3 NM from DER, 1544' right of centerline, up to 100' AGL/849' MSL.

CONWAY, SC

CONWAY-HORRY COUNTY (HYW)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1A 11237 (FAA)

TAKEOFF OBSTACLE NOTES: Rwy 4, trees beginning 58' from DER, 393' left of centerline, up to 108' AGL/147' MSL.

Rwy 22, trees beginning 184' from DER, 184' left of centerline, up to 86' AGL/125' MSL. Trees beginning 1508' from DER, 212' right of centerline, up to 73' AGL/112' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**

17229

CURRITUCK, NC

CURRITUCK COUNTY RGNL (ONX)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 1 09127 (FAA)

DEPARTURE PROCEDURE: **Rwy 5**, climb heading 045° to 1300 before proceeding on course. **Rwy 23**, climb heading 240° to 4000 before turning southbound.
TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 41' from DER, 166' left of centerline, up to 100' AGL/122' MSL. Tree 4058' from DER, 388' right of centerline, 100' AGL/124' MSL.
Rwy 23, trees beginning 60' from DER, 384' left of centerline, up to 100' AGL/115' MSL. Trees beginning 201' from DER, 427' right of centerline, up to 100' AGL/121' MSL.

DARLINGTON, SC

DARLINGTON COUNTY AIRPORT (UDG)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

ORIG-B 16119 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, multiple trees beginning 11' from DER, 241' left of centerline, up to 97' AGL/246' MSL. Multiple trees beginning 72' from DER, 29' right of centerline, up to 97' AGL/236' MSL.
Rwy 23, antenna 18' from DER, 263' left of centerline, 9' AGL/194' MSL. Trees beginning 241' from DER, 394' left of centerline, up to 70' AGL/249' MSL. Tree 732' from DER, 427' right of centerline, 33' AGL/212' MSL.

DILLON, SC

DILLON COUNTY (DLC)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 1 12208 (FAA)

TAKEOFF MINIMUMS: **Rwy 7**, 500-3 or std. w/min. climb of 250' per NM to 700.
DEPARTURE PROCEDURE: **Rwy 7**, climb heading 070° to 1400 before turning south. **Rwy 25**, climb heading 250° to 1900 before turning south.
TAKEOFF OBSTACLE NOTES: **Rwy 7**, trees beginning 77' from DER, 158' left of centerline, up to 100' AGL/214' MSL. Trees beginning 162' from DER, 494' right of centerline, up to 100' AGL/209' MSL. Tower 2.3 NM from DER, 2100' left of centerline, 370' AGL/510' MSL. **Rwy 25**, vehicles beginning 17' from DER, 313' left of centerline, up to 15' AGL/149' MSL. Vehicles beginning 28' from DER, 163' right of centerline, up to 15' AGL/149' MSL. Trees beginning 42' from DER, 256' left of centerline, up to 100' AGL/234' MSL. Trees beginning 182' from DER, 75' right of centerline, up to 100' AGL/244' MSL. Vehicles beginning 765' from DER, left and right of centerline, up to 17' AGL/156' MSL.

EDENTON, NC

NORTHEASTERN RGNL (EDE)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 09211 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 1**, trees beginning 23' from DER, left and right of centerline, up to 100' AGL/117' MSL. **Rwy 19**, poles beginning 1038' from DER, 567' left of centerline, 37' AGL/47' MSL. Trees beginning 1258' from DER, left and right of centerline, up to 100' AGL/114' MSL.

ELIZABETH CITY, NC

ELIZABETH CITY CG AIR STATION/RGNL
(ECG)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 14177 (FAA)

DEPARTURE PROCEDURE: **Note**: when tethered balloon located 2.6 NM SE of airport is flying: **Rwy 1**, climb on a heading between 190° CW 112° from DER. **Rwy 10**, climb on a heading between 280° CW 115° from DER. **Rwy 19**, climb on a heading between 154° CW 010° from DER. **Rwy 28**, climb on a heading between 163° CW 100° from DER.
TAKEOFF OBSTACLE NOTES: **Rwy 1**, box 53' from DER, 312' right of centerline, 6' AGL/13' MSL. Trees beginning 1233' from DER, 790' left of centerline, up to 41' AGL/44' MSL. **Rwy 10**, bldg 7' from DER, 442' right of centerline, 9' AGL/16' MSL. DME 292' from DER, 330' left of centerline, 17' AGL/24' MSL. Trees beginning 100' from DER, 373' right of centerline, up to 73' AGL/80' MSL. Trees beginning 2134' from DER, 408' left of centerline, up to 86' AGL/89' MSL. **Rwy 19**, taxiway sign 64' from DER 143' left of centerline, 3' AGL/12' MSL. Bushes beginning 76' from DER, 436' right of centerline, up to 10' AGL/17' MSL. Vehicles on road beginning 91' from DER, 86' right of centerline, up to 15' AGL/26' MSL. Pole and trees beginning 1032' from DER, 602' centerline, up to 71' AGL/78' MSL. Trees beginning 1996' from DER, 825' left of centerline, up to 100' AGL/107' MSL. **Rwy 28**, REILs beginning 26' from DER, 130' right of centerline, up to 2' AGL/12' MSL. Tree 2962' from DER, 1198' right of centerline, 81' AGL/88' MSL.

ELIZABETHTOWN, NC

CURTIS L BROWN JR FIELD (EYF)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 09183 (FAA)

DEPARTURE PROCEDURE: **Rwy 15**, climb heading 152° to 2100 before turning left. **Rwy 33**, climb heading 332° to 1100 before proceeding on course.
TAKEOFF OBSTACLE NOTES: **Rwy 15**, trees beginning 368' from DER, left and right of centerline, up to 100' AGL/214' MSL. **Rwy 33**, vehicle on road 177' from DER, 543' right of centerline, 15' AGL/144' MSL. Trees beginning 344' from DER, left and right of centerline, up to 100' AGL/229' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

17229

**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

ELKIN, NC

ELKIN MUNI (ZEF)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 14317 (FAA)

DEPARTURE PROCEDURE: **Rwy 7**, climb heading 074° to 2000 before turning north. **Rwy 25**, climb heading 255° to 2600 before turning north.

TAKEOFF OBSTACLE NOTES: **Rwy 7**, trees beginning 2' from DER, 133' left of centerline, up to 61' AGL/1120' MSL. Trees beginning 10' from DER, 64' right of centerline, up to 49' AGL/1048' MSL. Vehicles on road 169' from DER, 388' left of centerline, up to 15' AGL/1074' MSL. Trees beginning 665' from DER, 24' right of centerline, up to 50' AGL/1089' MSL. Trees beginning 931' from DER, 33' left of centerline, up to 93' AGL/1132' MSL. Trees beginning 1137' from DER, 249' right of centerline, up to 78' AGL/1097' MSL. Tower 1781' from DER, 452' right of centerline, 83' AGL/1082' MSL. Trees beginning 3265' from DER, 397' right of centerline, up to 100' AGL/1199' MSL. Tower 5075' from DER, 1290' left of centerline, 100' AGL/1179' MSL. **Rwy 25**, trees beginning 41' from DER, 125' left of centerline, up to 119' AGL/1138' MSL. Trees beginning 45' from DER, 92' right of centerline, up to 78' AGL/1137' MSL. Trees beginning 1217' from DER, 13' left of centerline, up to 99' AGL/1178' MSL. Trees beginning 1235' from DER, 55' right of centerline, up to 100' AGL/1219' MSL.

ERWIN, NC

HARNETT RGNL JETPORT (HRJ)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 07242 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, multiple trees beginning 1529' from DER 16' left of centerline, up to 96' AGL/297' MSL. Multiple trees beginning 2775' from DER, 111' right of centerline, up to 76' AGL/282' MSL. Multiple poles beginning 303' from DER, 445' left of centerline, up to 17' AGL/239' MSL. Pole beginning 671' from DER, 610' right of centerline, up to 38' AGL/239' MSL. **Rwy 23**, trees beginning 94' from DER, 206' right of centerline, up to 64' AGL/252' MSL. Trees beginning 5' from DER, 296' right of centerline, up to 59' AGL/247' MSL.

FAYETTEVILLE, NC

FAYETTEVILLE RGNL/GRANNIS FIELD (FAY)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 08213 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 4**, trees beginning 154' from DER, 117' right of centerline, up to 79' AGL/189' MSL. Trees beginning 344' from DER, 240' left of centerline, up to 63' AGL/173' MSL. **Rwy 10**, trees beginning 182' from DER, 295' right of centerline, up to 43' AGL/223' MSL. Trees beginning 451' from DER, 383' left of centerline, up to 62' AGL/242' MSL. **Rwy 22**, vehicle on road 98' from DER, left and right of centerline, up to 15' AGL/186' MSL. Trees beginning 1059' from DER, 551' right of centerline, up to 94' AGL/264' MSL. **Rwy 28**, pole and trees beginning 199' from DER, 307' left of centerline, up to 34' AGL/204' MSL. Trees beginning 593' from DER, 96' right of centerline, up to 79' AGL/239' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

FLORENCE, SC

FLORENCE RGNL (FLO)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 5 09071 (FAA)

DEPARTURE PROCEDURE: **Rwy 1**, climb on heading 021° to 1200 prior to turning left.

TAKEOFF OBSTACLE NOTES: **Rwy 1**, trees beginning 1929' from DER, 29' left of centerline up to 81' AGL/224' MSL. Trees beginning 1786' from DER, 239' right of centerline up to 89' AGL/232' MSL. Poles beginning 1628' from DER, 160' left and right of centerline up to 45' AGL/188' MSL. Antenna 341' from DER, 487' left of centerline up to 47' AGL/190' MSL. Floodlight 3262' from DER, 806' left of centerline up to 103' AGL/246' MSL. Floodlight 1498' from DER, 313' left of centerline up to 39' AGL/182' MSL. **Rwy 9**, trees beginning 3016' from DER, 635' left of centerline up to 91' AGL/212' MSL. Trees beginning 121' from DER, 14' right of centerline up to 97' AGL/218' MSL. Bushes beginning 32' from DER, 289' right of centerline up to 17' AGL/138' MSL. **Rwy 19**, trees beginning 174' from DER, 273' left of centerline up to 54' AGL/166' MSL. Trees beginning 811' from DER, 23' right of centerline up 69' AGL/181' MSL. Bushes beginning 20' from DER, 338' right of centerline up to 12' AGL/125' MSL. **Rwy 27**, trees beginning 102' from DER, 389' left of centerline up to 30' AGL/159' MSL.

FRANKLIN, NC

MACON COUNTY (1A5)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 09071 (FAA)

TAKEOFF MINIMUMS: **Rwys 7, 25**, Procedure NA at night. 5700-3, for climb in visual conditions.

DEPARTURE PROCEDURE: **Rwys 7, 25**, for climb in visual conditions remain within 3 NM of Macon County airport to cross airport south bound at or above 7600 via ODF R-349 to ODF VORTAC.

TAKEOFF OBSTACLE NOTES: **Rwy 7**, trees 599' from DER, 124' left of centerline, up to 38' AGL/2037' MSL. Vehicle on road 964' from DER, 720' left of centerline, 15' AGL/2054' MSL. Trees 1666' from DER, 620' right of centerline, up to 100' AGL/2179' MSL. Trees beginning 3090' from DER, 1270' left of and to centerline, up to 100' AGL/3139' MSL. Trees beginning 5665' from DER, 337' right of and to centerline, up to 100' AGL/2699' MSL. **Rwy 25**, vehicle on road 63' from DER, 318' left of centerline, 15' AGL/2054' MSL. Terrain 1000' from DER, on centerline, 2061' MSL. Trees beginning 1737' from DER, 848' left of and to centerline, up to 100' AGL/3519' MSL. Trees beginning 2460' from DER, 440' right of and to centerline, up to 100' AGL/3059' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)



GASTONIA, NC

GASTONIA MUNI (AKH)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 6 15232 (FAA)

DEPARTURE PROCEDURE: **Rwy 3**, climb heading 049° to 2700 before turning left. **Rwy 21**, climb heading 214° to 1600 before proceeding north.

TAKEOFF OBSTACLE NOTES: **Rwy 3**, trees beginning 162' from DER, 371' right of centerline, up to 105' AGL/844' MSL. Trees beginning 1200' from DER, 463' left of centerline, up to 76' AGL/835' MSL. Trees beginning 1965' from DER, 433' left of centerline, up to 80' AGL/859' MSL. Trees 3819' from DER, 657' right of centerline, up to 126' AGL/885' MSL. **Rwy 21**, pole 254' from DER, 336' right of centerline, 20' AGL/810' MSL. Pole 288' from DER, 329' left of centerline, 18' AGL/808' MSL. Tower and trees beginning 297' from DER, 467' left of centerline, up to 93' AGL/872' MSL. Trees beginning 1245' from DER, 558' right of centerline, up to 99' AGL/878' MSL.

GEORGETOWN, SC

GEORGETOWN COUNTY (GGE)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 14261 (FAA)

DEPARTURE PROCEDURE: **Rwy 29**, climb heading 289° to 600 before turning northbound.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 382' from DER, left and right of centerline, up to 97' AGL/122' MSL. **Rwy 11**, trees beginning 500' from DER, 200' left and right of centerline, up to 100' AGL/129' MSL. **Rwy 23**, trees beginning 177' from DER, 441' right of centerline, up to 100' AGL/111' MSL. Trees 1023' from DER, 670' left of centerline, up to 68' AGL/88' MSL. **Rwy 29**, trees beginning 880' from DER, left and right of centerline, up to 100' AGL/138' MSL.

GOLDSBORO, NC

WAYNE EXECUTIVE JETPORT (GWW)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1A 11321 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, tree 184' from DER, 494' right of centerline, 41' AGL/174' MSL. **Rwy 23**, trees beginning 107' from DER, 313' right of centerline, up to 109' AGL/ 242' MSL. Bush 101' from DER, 487' left of centerline, 9' AGL/142' MSL. Trees beginning 2212' from DER, 12' left of centerline, up to 98' AGL/231' MSL.

GREENSBORO, NC

PIEDMONT TRIAD INTL (GSO)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 09295 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5L**, trees beginning 1328' from DER, 524' left of centerline, up to 88' AGL/912' MSL. **Rwy 5R**, terrain and trees beginning 3' from DER, 499' right of centerline, up to 102' AGL/981' MSL. Trees beginning 2751' from DER, 1191' left of centerline, 57' AGL/966' MSL. **Rwy 14**, pole and railroad signal beginning 937' from DER, 604' right of centerline, up to 51' AGL/940' MSL. **Rwy 23L**, trees beginning 834' from DER, 719' left of centerline, up to 65' AGL/934' MSL. **Rwy 23R**, trees beginning 1195' from DER, 191' left of centerline, up to 100' AGL/970' MSL. Utility pole 170' from DER, 540' left of centerline, 33' AGL/936' MSL. Trees beginning 1715' from DER, 358' right of centerline, up to 100' AGL/967' MSL. **Rwy 32**, trees beginning 1' from DER, 289' right of centerline up to 90' AGL/1019' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017



TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

GREENVILLE, NC

PITT-GREENVILLE (PGV)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 5 16035 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 2**, ground beginning 50' from DER, 50' left of centerline, up to 31' MSL. Ground beginning 86' from DER, 291' right of centerline, up to 29' MSL. Trees beginning 975' from DER, 688' right of centerline, up to 86' AGL/124' MSL. Trees beginning 1779' from DER, 653' right of centerline, up to 96' AGL/125' MSL. Tree 1910' from DER, 989' left of centerline, 63' AGL/89' MSL. Trees beginning 2224' from DER, 655' right of centerline, up to 115' AGL/142' MSL. Trees beginning 2562' from DER, 583' left of centerline, up to 82' AGL/134' MSL. Trees beginning 3164' from DER, 719' left of centerline, up to 107' AGL/138' MSL. **Rwy 8**, building, poles, road and trees beginning 79' from DER, 298' left of centerline, up to 87' AGL/113' MSL. Trees and road beginning 144' from DER, 456' right of centerline, up to 44' AGL/66' MSL. Building, poles and trees beginning 795' from DER, 65' right of centerline, up to 59' AGL/71' MSL. Trees and poles beginning 1009' from DER, 14' left of centerline, up to 90' AGL/119' MSL. Building, poles and trees beginning 1538' from DER, 279' right of centerline, up to 62' AGL/88' MSL. Trees beginning 2334' from DER, 307' right of centerline, up to 88' AGL/110' MSL. Trees beginning 2336' from DER, 7' left of centerline, up to 101' AGL/127' MSL. Trees beginning 3324' from DER, 646' right of centerline, up to 99' AGL/125' MSL. **Rwy 20**, runway lighting 40' from DER, 148' right of centerline, 6' AGL/25' MSL. Runway lighting and sign beginning 40' from DER, 149' left of centerline, up to 5' AGL/25' MSL. Vehicles on road, bridge/overpass, and trees beginning 230' from DER, 245' left of centerline, up to 26' AGL/42' MSL. NAVAID 491' from DER, 280' right of centerline, 35' AGL/44' MSL. Trees beginning 1133' from DER, 745' left of centerline, up to 103' AGL/115' MSL. Trees beginning 1354' from DER, 751' right of centerline, up to 113' AGL/125' MSL. Transmission line towers and trees beginning 2412' from DER, crossing left to right of centerline, up to 112' AGL/122' MSL. Trees beginning 2673' from DER, crossing centerline, up to 100' AGL/159' MSL. Trees beginning 3930' from DER, 432' left of centerline, up to 102' AGL/162' MSL. Trees beginning 5002' from DER, 706' left of centerline, up to 93' AGL/164' MSL. **Rwy 26**, airport sign 40' from DER, 199' left of centerline, 4' AGL/26' MSL. Runway end identifier light, 41' from DER, 150' right of centerline, 2' AGL/26' MSL. Trees beginning 152' from DER, 354' right of centerline, up to 86' AGL/117' MSL. Trees beginning 336' from DER, 504' left of centerline, up to 25' AGL/38' MSL. Trees beginning 573' from DER, 229' left of centerline, up to 106' AGL/109' MSL. Trees beginning 1330' from DER, 170' left of centerline, up to 109' AGL/112' MSL. Trees beginning 1625' from DER, crossing centerline, up to 127' AGL/130' MSL. Trees beginning 2122' from DER, crossing centerline, up to 131' AGL/134' MSL.

GREENVILLE, SC

DONALDSON FIELD (GYH)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG-A 15288 (FAA)

TAKEOFF MINIMUMS: **Rwy 5**, 300-1¼ or std. w/ min. climb of 220' per NM to 1300, or alternatively, w/ standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1800' prior to DER.
TAKEOFF OBSTACLE NOTES: **Rwy 5**, fence 63' from DER, 457' right of centerline, 8' AGL/921' MSL. Trees beginning 874' from DER, 723' left of centerline, up to 67' AGL/976' MSL. Trees beginning 1088' from DER, 129' right of centerline, up to 82' AGL/998' MSL. Tower 1.5 NM from DER, 2224' left of centerline, 250' AGL/1167' MSL.

GREENVILLE DOWNTOWN (GMU)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 7 15288 (FAA)

TAKEOFF MINIMUMS: **Rwy 10**, 300-1 or std. w/min. climb of 355' per NM to 1300. **Rwy 28**, 300-2½ or std. w/min. climb of 220' per NM to 1500, or alternatively, with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1900' prior to DER.

DEPARTURE PROCEDURE: **Rwy 1**, climb heading 006° to 2800 before turning west or northwest. **Rwy 10**, climb heading 096° to 1800 before turning west or northwest.

Rwy 19, climb heading 186° to 1800 before turning north. **Rwy 28**, climb heading 276° to 2300 before turning north or northwest.

TAKEOFF OBSTACLE NOTES: **Rwy 1**, sign 26' from DER, 125' left of centerline, 3' AGL/1049' MSL. Building and poles beginning 195' from DER, 374' right of centerline, up to 48' AGL/1111' MSL. Trees beginning 350' from DER, 319' left of centerline, up to 88' AGL/1129' MSL. Sign, building, poles, and trees beginning 1050' from DER, 55' right of centerline, up to 52' AGL/1188' MSL. Buildings 4064' from DER, 384' right of centerline, up to 61' AGL/1174' MSL. **Rwy 10**, sign and trees beginning 18' from DER, 48' right of centerline, up to 31' AGL/1026' MSL. Sign 21' from DER, 124' left of centerline, 3' AGL/1017' MSL. Pole and trees beginning 9' from DER, 198' right of centerline, up to 56' AGL/1057' MSL. Trees beginning 498' from DER, 50' left of centerline, up to 51' AGL/1042' MSL. Trees beginning 1821' from DER, 603' left of centerline, up to 47' AGL/1068' MSL. Building and pole beginning 3337' from DER, 539' right of centerline, up to 105' AGL/1136' MSL. Tower 5213' from DER, 810' left of centerline, 152' AGL/1173' MSL. **Rwy 19**, signs beginning 11' from DER, 71' right of centerline, up to 3' AGL/991' MSL. Trees beginning 173' from DER, 492' right of centerline, up to 45' AGL/1013' MSL. Pole and trees beginning 276' from DER, 527' left of centerline, up to 33' AGL/1003' MSL. Trees beginning 2809' from DER, 763' right of centerline, up to 83' AGL/1094' MSL. **Rwy 28**, signs beginning 13' from DER, 77' left of centerline, up to 3' AGL/1000' MSL. Pole and trees beginning 45' from DER, 285' right of centerline, up to 49' AGL/1043' MSL. Poles and trees beginning 194' from DER, 251' left of centerline, up to 56' AGL/1021' MSL. Trees beginning 532' from DER, 60' right of centerline, up to 95' AGL/1047' MSL. Trees beginning 850' from DER, 323' left of centerline, up to 71' AGL/1075' MSL. Building 1.9 NM from DER, 2143' right of centerline, 332' AGL/1316' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

GREENWOOD, SC

GREENWOOD COUNTY (GRD)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 16315 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5:** Tree 387' from DER, 289' right of centerline, 100' AGL/629' MSL. **Rwy 09:** trees beginning 215' from DER, 493' left of centerline, up to 643' MSL. Tree 444' from DER, 554' left of centerline, 647' MSL. Trees beginning 568' from DER, 253' left of centerline, up to 651' MSL. Trees beginning 627' from DER, 545' right of centerline, up to 646' MSL. Trees beginning 780' from DER, 265' left of centerline, up to 663' MSL. Tree and pole beginning 899' from DER, 308' left of centerline, up to 668' MSL. Tree 2090' from DER, 1000' right of centerline, 109' AGL/691' MSL. Tree 2692' from DER, 1038' left of centerline, 86' AGL/699' MSL. Trees beginning 2096' from DER, 512' left of centerline, up to 100' AGL/719' MSL. Trees beginning 3359' from DER, 546' right of centerline, 100' AGL/709' MSL. Trees beginning 3773' from DER, 550' right of centerline, up to 100' AGL/719' MSL. **Rwy 23:** trees beginning 812' from DER, 571' left of centerline, up to 657' MSL. Tree 963' from DER, 516' left of centerline, 670' MSL. Trees, beginning 1037' from DER, 291' left of centerline, up to 61' AGL/681' MSL. Trees, beginning 1323' from DER, 10' left of centerline, up to 100' AGL/719' MSL. Tree 1761' from DER, 413' right of centerline, 673' MSL. Tree 1933' from DER, 244' right of centerline, 86' AGL/677' MSL. Trees, beginning 2581' from DER, 72' right of centerline, up to 100' AGL/719' MSL. Trees, beginning 3865' from DER, 1179' right of centerline, up to 100' AGL/729' MSL. **Rwy 27:** bush 11' from DER, 274' left of centerline, 3' AGL/634' MSL. Tree 264' from DER, 550' left of centerline, 641' MSL. Tree 300' from DER, 549' right of centerline, 652' MSL. Trees beginning 424' from DER, 543' left of centerline, up to 649' MSL. Tree 467' from DER, 587' right of centerline, 669' MSL. Tree 562' from DER, 639' right of centerline, 680' MSL. Trees beginning 670' from DER, 10' right of centerline, up to 85' AGL/716' MSL. Trees beginning 725' from DER, 588' left of centerline, up to 653' MSL. Trees beginning 966' from DER, 594' left of centerline, up to 686' MSL. Trees beginning 1087' from DER, 657' left of centerline, up to 695' MSL. Trees beginning 1681' from DER, 695' left of centerline, up to 707' MSL. Trees beginning 1864' from DER, 34' left of centerline, up to 714' MSL. Trees beginning 2764' from DER, 159' left of centerline, up to 718' MSL. Trees beginning 2959' from DER, 119' right of centerline, up to 726' MSL. Trees beginning 2965' from DER, 11' left of centerline, up to 727' MSL. Trees beginning 3332' from DER, 561' right of centerline, up to 100' AGL/739' MSL. Trees beginning 3477' from DER, 572' left of centerline, 100' AGL/729' MSL. Trees beginning 3724' from DER, 550' left of centerline, 100' AGL/739' MSL. Trees beginning 3746' from DER, 790' right of centerline, 100' AGL/749' MSL.

HARTSVILLE, SC

HARTSVILLE RGNL (HVS)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 17229 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 3,** buildings, tank beginning 5' from DER, 336' right of centerline, up to 368' MSL. Bushes, tree beginning 31' from DER, 127' left of centerline, up to 384' MSL. Pole, tank, building beginning 68' from DER, 380' right of centerline, up to 385' MSL. Bushes beginning 381' from DER, 501' left of centerline, up to 385' MSL. Trees beginning 410' from DER, 507' right of centerline, up to 430' MSL. Trees, poles, buildings beginning 541' from DER, 244' left of centerline, up to 444' MSL. Trees, poles beginning 541' from DER, 13' right of centerline, up to 432' MSL. Tree 786' from DER, 632' left of centerline, 462' MSL. Trees beginning 900' from DER, 11' left of centerline, up to 467' MSL. Trees, poles beginning 1042' from DER, 2' left of centerline, up to 471' MSL. Trees, poles beginning 1402' from DER, 3' right of centerline, up to 436' MSL. Trees beginning 2040' from DER, 616' right of centerline, up to 437' MSL. Trees beginning 2119' from DER, 6' right of centerline, up to 440' MSL. Trees beginning 2251' from DER, 103' right of centerline, up to 443' MSL. Trees beginning 2355' from DER, 105' right of centerline, up to 445' MSL. Trees beginning 2363' from DER, 47' right of centerline, up to 450' MSL. Trees beginning 2455' from DER, 97' right of centerline, up to 453' MSL. Trees beginning 2534' from DER, 13' right of centerline, up to 454' MSL. Trees, pole beginning 2662' from DER, 14' right of centerline, up to 460' MSL. Trees, poles beginning 2756' from DER, 78' left of centerline, up to 473' MSL. Trees beginning 3076' from DER, 655' left of centerline, up to 475' MSL. Trees, pole beginning 3102' from DER, 16' left of centerline, up to 478' MSL. Trees beginning 3200' from DER, 27' right of centerline, up to 465' MSL. Trees beginning 3456' from DER, 758' right of centerline, up to 466' MSL. Trees beginning 3505' from DER, 12' left of centerline, up to 480' MSL. Trees beginning 3532' from DER, 652' right of centerline, up to 469' MSL. Trees beginning 3580' from DER, 197' right of centerline, up to 471' MSL. Trees beginning 3619' from DER, 490' right of centerline, up to 473' MSL. Trees beginning 3625' from DER, 103' right of centerline, up to 480' MSL. Trees beginning 3720' from DER, 208' right of centerline, up to 487' MSL. Trees beginning 3809' from DER, 117' right of centerline, up to 489' MSL. Trees beginning 4023' from DER, 204' right of centerline, up to 493' MSL. Trees beginning 4139' from DER, 251' right of centerline, up to 495' MSL. Trees, transmission tower beginning 4249' from DER, 55' left of centerline, up to 485' MSL. **Rwy 21,** trees beginning 21' from DER, 459' left of centerline, up to 402' MSL. Buildings beginning 95' from DER, 440' right of centerline, up to 360' MSL. Pole, building, tree beginning 263' from DER, 410' right of centerline, up to 365' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

GREER, SC

GREENVILLE SPARTANBURG INTL (GSP)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1A 15288 (FAA)

DEPARTURE PROCEDURE: **Rwy 4,** climb heading 038° to 2500 before turning left.

TAKEOFF OBSTACLE NOTES: **Rwy 4,** trees 1422' from DER, 832' right of centerline, up to 65' AGL/1001' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

HATTERAS, NC

BILLY MITCHELL (HSE)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 09267 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 7**, trees beginning 388' from DER, left of centerline, up to 100' AGL/169' MSL. **Rwy 25**, trees 512' from DER, 103' right of centerline, 100' AGL/110' MSL. Boat mast 2107' from DER, 664' left of centerline, 100' AGL/100' MSL.

HICKORY, NC

HICKORY RGNL (HKY)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 4 11237 (FAA)

DEPARTURE PROCEDURE: Use HICKORY DEPARTURE.

HILTON HEAD ISLAND, SC

HILTON HEAD (HXD)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 03191 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 3**, numerous trees 328' from DER, 428' left of DER, 86' AGL/106' MSL. Numerous trees 319' from DER, 390' right of DER, 83' AGL/97' MSL. **Rwy 21**, numerous trees 39' from DER, 357' right of DER, 94' AGL/111' MSL. Numerous trees 368' from DER, 332' left of DER, 73' AGL/87' MSL. Numerous trees 1421' from DER, 221' right of DER, 74' AGL/91' MSL. Numerous trees 1207' from DER, 329' left of DER, 85' AGL/99' MSL.

JACKSONVILLE, NC

ALBERT J. ELLIS (OAJ)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 2 12264 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, vehicles on road 93' from DER, left and right of centerline, up to 15' AGL/107' MSL. Pole 1319' from DER, 830' left of centerline, 44' AGL/127' MSL. Trees beginning 1678' from DER, left and right of centerline up to 100' AGL/198' MSL. **Rwy 23**, vehicles on road 233' from DER, 221' left of centerline, up to 15' AGL/107' MSL. Trees beginning 2091' from DER, left and right of centerline, up to 100' AGL/192' MSL.

JEFFERSON, NC

ASHE COUNTY (GEV)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 17117 (FAA)

TAKEOFF MINIMUMS: **Rwy 28**, 700-3 w/min. climb of 425' per NM to 5500 or standard w/min. climb of 750' per NM to 4900 or 2200-3 for climb in visual conditions. DEPARTURE PROCEDURE: **Rwy 10**, climb heading 096° to 4400 before proceeding on course. **Rwy 28**, climb heading 276° to 6100 before proceeding on course. VCOA: **Rwy 28**, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Ashe County Airport at or above 5200 before proceeding on course.

TAKEOFF OBSTACLE NOTES: **Rwy 10**, NAVAID, runway light, and bush beginning 8' from DER, 17' right of centerline, up to 3' AGL/3088' MSL. NAVAID, runway light, and bush beginning 8' from DER, 17' left of centerline, up to 4' AGL/3089' MSL. Trees beginning 344' from DER, 231' right of centerline, up to 3109' MSL. Trees beginning 369' from DER, 236' right of centerline, up to 3114' MSL. **Rwy 28**, terrain, antenna, runway light, and tree beginning 23' from DER, 6' left of centerline, up to 3250' MSL. Terrain 25' from DER, 176' right of centerline, 3183' MSL. Terrain, runway light, building, agricultural equipment, and tree beginning 100' from DER, 22' right of centerline, up to 3241' MSL. Trees beginning 1091' from DER, 6' right of centerline, up to 3306' MSL. Trees beginning 6071' from DER, 1669' right of centerline, up to 3422' MSL. Tree 1.0 NM from DER, 1990' right of centerline, 3490' MSL. Trees beginning 1.0 NM from DER, 1487' right of centerline, up to 3497' MSL. Trees beginning 1.0 NM from DER, 1330' right of centerline, up to 3564' MSL. Trees beginning 1.0 NM from DER, 1599' right of centerline, up to 3644' MSL. Trees beginning 1 NM from DER, 1185' right of centerline, up to 3731' MSL. Pole and trees beginning 1.1 NM from DER, 513' right of centerline, up to 3831' MSL. Tree 2.5 NM from DER, 1194' right of centerline, 3597' MSL.

KENANSVILLE, NC

DUPLIN COUNTY (DPL)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 09015 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 30' from DER, 156' right of centerline, up to 100' AGL/238' MSL. Trees beginning 1915' from DER, 126' left of centerline, up to 100' AGL/231' MSL. Vehicles on road 641' from DER, left and right of centerline, up to 17' AGL/156' MSL. **Rwy 23**, trees beginning 12' from DER, 329' left of centerline, up to 100' AGL/218' MSL. Trees beginning 16' from DER, 59' right of centerline, up to 100' AGL/225' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**

KILL DEVIL HILLS, NC

FIRST FLIGHT (FFA)

**TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES**

ORIG 17173 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 21**, tree, 11' from DER, 481' right of centerline, 79' MSL. Trees beginning 12' from DER, 277' right of centerline, up to 91' MSL. Trees beginning 18' from DER, 149' right of centerline, up to 93' MSL. Tree, 20' from DER, 318' left of centerline, 71' MSL. Trees beginning 42' from DER, 213' left of centerline, up to 75' MSL. Trees beginning 115' from DER, 150' left of centerline, up to 79' MSL. Trees beginning 212' from DER, 142' left of centerline, up to 81' MSL. Trees beginning 334' from DER, 155' left of centerline, up to 84' MSL. Trees beginning 347' from DER, 162' left of centerline, up to 85' MSL. Trees beginning 441' from DER, 167' left of centerline, up to 86' MSL. Trees beginning 483' from DER, 340' right of centerline, up to 94' MSL. Trees beginning 497' from DER, 205' right of centerline, up to 95' MSL. Tree, pole beginning 616' from DER, 192' right of centerline, up to 97' MSL. Tree, 2798' from DER, 876' left of centerline, 90' MSL. Antenna 2852' from DER, 470' left of centerline, 110' MSL. **Rwy 3**, trees beginning 2' from DER, 214' left of centerline, up to 71' MSL. Tree, building beginning 88' from DER, 28' left of centerline, up to 75' MSL. Pole, 339' from DER, 201' right of centerline, 21' MSL. Trees beginning 365' from DER, 37' right of centerline, up to 25' MSL. Tree, 454' from DER, 207' right of centerline, 30' MSL. Trees beginning 467' from DER, 64' right of centerline, up to 34' MSL. Tree, 731' from DER, 274' right of centerline, 35' MSL. Pole beginning 1301' from DER, 236' right of centerline, up to 105' MSL. Pole beginning 2109' from DER, 133' left of centerline, up to 105' MSL.

KINGSTREE, SC

WILLIAMSBURG RGNL (CKI)

**TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES**

AMDT 2 17229 (FAA)

TAKEOFF MINIMUMS: **Rwy 14**, 400-2³/₄ or std. w/ min. climb of 210'/NM to 500.

DEPARTURE PROCEDURE: **Rwy 14**, climb heading 140° to 700 before turning north.

TAKEOFF OBSTACLE NOTES: **Rwy 14**, tree 23' from DER, 159' right of centerline, 6' AGL/66' MSL. Parking lot beginning 199' from DER, 478' left of centerline, up to 77' MSL. Building 359' from DER, 578' left of centerline, 81' MSL. Tree, pole beginning 880' from DER, 473' left of centerline, up to 142' MSL. Trees beginning 1083' from DER, 548' right of centerline, up to 130' MSL. Trees beginning 1181' from DER, 680' left of centerline, up to 145' MSL. Trees beginning 1574' from DER, 631' left of centerline, up to 152' MSL. Trees beginning 1918' from DER, 590' right of centerline, up to 138' MSL. Trees beginning 2175' from DER, 633' right of centerline, up to 142' MSL. Trees beginning 2701' from DER, 874' right of centerline, up to 151' MSL. Trees beginning 2896' from DER, 551' left of centerline, up to 159' MSL. Tree 3483' from DER, 1366' right of centerline, 160' MSL. Trees beginning 3483' from DER, 597' right of centerline, up to 163' MSL. Tree 3805' from DER, 596' right of centerline, 165' MSL. Tower 2.2 NM from DER, 2801' right of centerline, 330' AGL/404' MSL. **Rwy 32**, trees beginning 62' from DER, 325' left of centerline, up to 107' MSL. Trees beginning 126' from DER, 507' right of centerline, up to 86' AGL/150' MSL. Trees beginning 140' from DER, 427' left of centerline, up to 123' MSL. Tree 1024' from DER, 733' left of centerline, 143' MSL. Trees beginning 1138' from DER, 634' left of centerline, up to 147' MSL. Trees beginning 1249' from DER, 723' right of centerline, up to 158' MSL. Trees beginning 1472' from DER, 614' right of centerline, up to 162' MSL. Trees beginning 1877' from DER, 621' left of centerline, up to 148' MSL. Trees beginning 2328' from DER, 580' left of centerline, up to 153' MSL. Trees beginning 2541' from DER, 572' left of centerline, up to 155' MSL. Tree 3442' from DER, 1019' left of centerline, 157' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**

17229

KINSTON, NC

KINSTON RGNL JETPORT AT

STALLINGS FIELD (ISO)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 07298 (FAA)

DEPARTURE PROCEDURE: **Rwy 5**, climb heading 050° to 1800 before turning east.

TAKEOFF OBSTACLE NOTES: **Rwy 14**, tree 23' from DER, 159' right of centerline, 6' AGL/66' MSL. Parking lot beginning 199' from DER, 478' left of centerline, up to 77' MSL. Building 359' from DER, 578' left of centerline, 81' MSL. Tree, pole beginning 880' from DER, 473' left of centerline, up to 142' MSL. Trees beginning 1083' from DER, 548' right of centerline, up to 130' MSL. Trees beginning 1181' from DER, 680' left of centerline, up to 145' MSL. Trees beginning 1574' from DER, 631' left of centerline, up to 152' MSL. Trees beginning 1918' from DER, 590' right of centerline, up to 138' MSL. Trees beginning 2175' from DER, 633' right of centerline, up to 142' MSL. Trees beginning 2701' from DER, 874' right of centerline, up to 151' MSL. Trees beginning 2896' from DER, 551' left of centerline, up to 159' MSL. Tree 3483' from DER, 1366' right of centerline, 160' MSL. Trees beginning 3483' from DER, 597' right of centerline, up to 163' MSL. Tree 3805' from DER, 596' right of centerline, 165' MSL. Tower 2.2 NM from DER, 2801' right of centerline, 330' AGL/404' MSL. **Rwy 32**, trees beginning 62' from DER, 325' left of centerline, up to 107' MSL. Trees beginning 126' from DER, 507' right of centerline, up to 86' AGL/150' MSL. Trees beginning 140' from DER, 427' left of centerline, up to 123' MSL. Tree 1024' from DER, 733' left of centerline, 143' MSL. Trees beginning 1138' from DER, 634' left of centerline, up to 147' MSL. Trees beginning 1249' from DER, 723' right of centerline, up to 158' MSL. Trees beginning 1472' from DER, 614' right of centerline, up to 162' MSL. Trees beginning 1877' from DER, 621' left of centerline, up to 148' MSL. Trees beginning 2328' from DER, 580' left of centerline, up to 153' MSL. Trees beginning 2541' from DER, 572' left of centerline, up to 155' MSL. Tree 3442' from DER, 1019' left of centerline, 157' MSL.

LAKE CITY, SC

LAKE CITY MUNI CJ EVANS FIELD (51J)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 07074 (FAA)

TAKEOFF MINIMUMS: **Rwy 1**, 500-2½ or std. w/ min. climb of 375' per NM to 700. **Rwy 19**, 300-1 or std. w/ min. climb of 404' per NM to 400.

TAKEOFF OBSTACLE NOTES: **Rwy 1**, tree 1474' from DER, 189' right of centerline, 62' AGL/143' MSL. Multiple towers beginning 1.6 NM from DER, 1285' left of centerline, up to 411' AGL/491' MSL. **Rwy 19**, tree 1428' from DER, 225' right of centerline, 53' AGL/134' MSL. Tank 4906' from DER, 1349' left of centerline, 180' AGL/254' MSL.

LANCASTER, SC

LANCASTER COUNTY- MCWHIRTER

FIELD (LKR)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 2 15232 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 6**, trees 176' from DER, 394' left of centerline, up to 27' AGL/526' MSL. Trees 4704' from DER, 1425' left of centerline, up to 81' AGL/630' MSL. **Rwy 24**, trees 73' from DER, 492' left of centerline, up to 18' AGL/467' MSL.

LAURENS, SC

LAURENS COUNTY (LUX)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 13122 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 8**, trees and bushes beginning 72' from DER, 298' right of centerline, up to 68' AGL/787' MSL. Vehicles on roadway, poles and trees beginning 929' from DER, 5' left of centerline, up to 120' AGL/789' MSL. Rising terrain and trees beginning 944' from DER, 1' right of centerline, up to 106' AGL/777' MSL. Vehicles on roadway beginning 955' from DER, left and right of centerline up to 15' AGL/734' MSL. Building 1013' from DER, 662' right of centerline, 18' AGL/729' MSL. Fence beginning 1051' from DER, 434' right of centerline, 2' AGL/723' MSL. **Rwy 26**, trees beginning 104' from DER, 470' right of centerline, up to 128' AGL/799' MSL. Trees beginning 580' from DER, 169' left of centerline, up to 117' AGL/766' MSL. Trees beginning 915' from DER, 113' right of centerline, up to 110' AGL/768' MSL.

LEXINGTON, NC

DAVIDSON COUNTY (EXX)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 12208 (FAA)

TAKEOFF MINIMUMS: **Rwy 6**, 300-1 or std. w/min. climb of 384' per NM to 1000.

TAKEOFF OBSTACLE NOTES: **Rwy 6**, trees beginning 917' from DER 34' right of centerline, up to 100' AGL/856' MSL. Trees beginning 158' from DER, 8' left of centerline, up to 100' AGL/859' MSL. Tanks 1520' from DER, 121' left of centerline, up to 110' AGL/755' MSL. **Rwy 24**, tree 53' from DER, 472' left of centerline, 100' AGL/774' MSL. Terrain beginning 150' from DER, 223' right of centerline, 754' MSL.

17229

**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

LIBERTY, NC

CAUSEY (2A5)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 97254 (FAA)

TAKEOFF MINIMUMS: **Rwys 2, 20**, 300-1.DEPARTURE PROCEDURE: **Rwy 20**, for departures 245° CW 020°, climbing left turn direct LIB VORTAC, then proceed outbound via LIB R-256 to 3000 before proceeding on course.

LINCOLNTON, NC

LINCOLNTON COUNTY RGNL (IPJ)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 2 15232 (FAA)

DEPARTURE PROCEDURE: **Rwy 5**, climb heading 063° to 2000 before proceeding on course. **Rwy 23**, climb heading 243° to 2800 before turning left.TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 1913' from DER, 330' left of centerline, up to 75' AGL/954' MSL. **Rwy 23**, trees beginning 2068' from DER, 479' right of centerline, up to 102' AGL/1001' MSL. Trees 2572' from DER, 42' left of centerline, up to 87' AGL/986' MSL. Trees 5326' from DER, 1643' right of centerline, up to 88' AGL/1027' MSL.

LORIS, SC

TWIN CITY (5J9)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 10126 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 8**, vehicles on roadway 18' from DER, 127' right of centerline, up to 15' AGL/119' MSL. Trees beginning 159' from DER, 208' right of centerline, up to 100' AGL/204' MSL. Trees beginning 169' from DER, 314' left of centerline, up to 100' AGL/204' MSL.**Rwy 26**, vehicles on roadway 9' from DER, 113' left of centerline, up to 15' AGL/119' MSL. Trees beginning 20' from DER, 182' left of centerline, up to 100' AGL/204' MSL. Hangar 81' from DER, 267' right of centerline, 50' AGL/154' MSL. Aircraft 87' from DER, 171' right of centerline, up to 30' AGL/134' MSL. Building 665' from DER, 139' left of centerline, 30' AGL/134' MSL. Building 1359' from DER, 226' right of centerline, 30' AGL/134' MSL.

LOUISBURG, NC

TRIANGLE NORTH EXECUTIVE (LHZ)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 11293 (FAA)

DEPARTURE PROCEDURE: **Rwy 5**, climb heading 046° to 1900 before turning right.TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 154' from DER, 516' right of centerline, up to 99' AGL/399' MSL. Trees beginning 166' from DER, 492' left of centerline, up to 75' AGL/415' MSL. Terrain 471' from DER, 394' left of centerline, 345' MSL. **Rwy 23**, vehicle on road 98' from DER, 457' right of centerline, up to 15' AGL/377' MSL. Power line 760' from DER, 635' right of centerline, 55' AGL/405' MSL.

LUMBERTON, NC

LUMBERTON RGNL (LBT)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 3 14289 (FAA)

TAKEOFF MINIMUMS: **Rwy 31**, 300-1 or std. w/min.

climb of 250' per NM to 400 or alternatively, with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 2000' prior to DER.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, utility 29' from DER, 117' left of centerline, 3' AGL/124' MSL. Trees beginning 93' from DER, 335' right of centerline, up to 55' AGL/180' MSL. Trees beginning 1780' from DER, left and right of centerline, up to 93' AGL/219' MSL. **Rwy 13**, vehicles on roadway beginning 29' from DER, 392' right of centerline, up to 15' AGL/139' MSL. Vehicles on roadway beginning 340' from DER, 123' left of centerline, up to 15' AGL/139' MSL. Trees beginning 486' from DER, left and right of centerline, up to 100' AGL/219' MSL. **Rwy 23**, trees beginning 59' from DER, 119' right of centerline, up to 107' AGL/233' MSL. Trees beginning 3274' from DER, 31' left of centerline, up to 91' AGL/217' MSL. **Rwy 31**, vehicles on roadway beginning 258' from DER, 532' left of centerline, up to 15' AGL/139' MSL. Building 510' from DER, 612' left of centerline, 40' AGL/164' MSL. Trees beginning 436' from DER, left and right of centerline, up to 100' AGL/224' MSL. Tower 5168' from DER, 1713' right of centerline, 150' AGL/286' MSL.

MANNING, SC

SANTEE COOPER RGNL (MNI)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 09043 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 2**, trees beginning at DER, 480' right of centerline, up to 100' AGL/229' MSL. Trees beginning 16' from DER, 221' left of centerline, up to 100' AGL/209' MSL. Vehicle on road 85' from DER, 468' right of centerline, 15' AGL/117' MSL. **Rwy 20**, trees beginning 125' from DER, 289' right of centerline, up to 100' AGL/179' MSL. Trees beginning 86' from DER, 136' left of centerline, up to 100' AGL/189' MSL. Vehicle on road 250' from DER, on centerline, 15' AGL/110' MSL.

MANTEO, NC

DARE COUNTY RGNL (MQI)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 2 11349 (FAA)

TAKEOFF MINIMUMS: **Rwy 17**, 300-1½ or std. w/min. climb of 250' per N to 300. **Rwy 35**, 300-1½ or std. w/min. climb of 260' per NM to 300.TAKEOFF OBSTACLE NOTES: **Rwy 5**, multiple trees beginning 585' from DER, 417' left and right of centerline, up to 100' AGL/109' MSL. **Rwy 35**, multiple trees beginning 23' from DER, 182' right and left of centerline, up to 100' AGL/116' MSL. Building 267' from DER, 410' right of centerline, 20' AGL/35' MSL. Ship 1 NM from DER, on centerline, 208' AGL/208' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

MARION, SC

MARION COUNTY (MAO)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 14317 (FAA)

DEPARTURE PROCEDURE: **Rwy 4**, climb on heading 058° to 2000 before turning.

TAKEOFF OBSTACLE NOTES: **Rwy 4**, road with vehicle 89' from DER, 241' left of centerline, 15' AGL/103' MSL. Trees and bushes beginning 8' from DER, 301' left of centerline, up to 15' AGL/92' MSL. Buildings beginning 271' from DER, 385' left of centerline up to 25' AGL/114' MSL. Trees and poles beginning 297' from DER, 401' left of centerline, up to 51' AGL/140' MSL. Trees beginning 1311' from DER, 411' left of centerline, up to 107' AGL/201' MSL. Trees and bushes beginning 14' from DER, 258' right of centerline, up to 67' AGL/154' MSL. Trees, buildings, and poles beginning 511' from DER, 216' right of centerline, up to 125' AGL/214' MSL. Trees beginning 2026' from DER, 7' right of centerline, up to 91' AGL/188' MSL. **Rwy 22**, road with vehicle 96' from DER, 489' left of centerline, 15' AGL/104' MSL. Trees beginning 226' from DER, 302' left of centerline, up to 48' AGL/136' MSL. Trees beginning 1019' from DER, 372' left of centerline, up to 47' AGL/135' MSL. Bush 4' from DER, 354' right of centerline, 12' AGL/101' MSL. Trees beginning 2624' from DER, 811' right of centerline, up to 109' AGL/197' MSL.

MAXTON, NC

LAURINBURG-MAXTON (MEB)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 07298 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, road 606' from DER, on centerline, 15' AGL/224' MSL. Trees 1002' from DER, 474' left of centerline, 67' AGL/267' MSL. **Rwy 13**, aircraft 762' from DER, 762' left of centerline, 58' AGL/266' MSL. **Rwy 23**, tree 1011' from DER, 512' right of centerline, 30' AGL/246' MSL. **Rwy 31**, trees beginning 1014' from DER, 58' left of centerline, up to 54' AGL/271' MSL.

MC ENTIRE JNGB (MMT)

EASTOVER, SC
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 14149

TAKEOFF MINIMUMS: **Rwy 5**, Standard with CG of 310 ft/NM to 2700 or 300-2 with min climb of 250 ft/NM to 2700 (Provided a ceiling and visibility to see and avoid a 40:1 penetration within the ICA (extended) and a climb gradient to avoid a 40:1 penetration outside the ICA (extended)). **Rwy 32**, Standard with CG of 230ft/NM to 2700.

DEPARTURE PROCEDURE: **Rwy 5**, depart on a track of 050 to 2700° before turning on course, or as directed by ATC. **Rwy 32**, depart on a track of 320 to 700° MSL before turning on course, or as directed by ATC. Departing eastbound, complete turn within 4 NM to avoid R-6001, if unable, advise Control Tower prior to taxi.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, Helicopters parked from 198' to 552' from DER, 306' to 618' left of centerline, up to 19' AGL/274' MSL. Multiple trees left of centerline, beginning 2390' out to 1.5 NM from DER, 93' to 2082' left of centerline, 0' AGL/385' MSL up to 551' MSL. Multiple trees right of centerline, beginning 2207' out to 4124' from DER, 232' to 905' right of centerline, 0' AGL/377' MSL up to 399' MSL. **Rwy 14**, Multiple trees left of centerline, beginning 2316' out to 4208' from DER, 774' to 1107' left of centerline, 0' AGL/325' MSL up to 359' MSL. Pylon 3282' from DER, 1553' left of centerline, 79' AGL/288' MSL. Multiple trees right of centerline, beginning 2202' out to 3374' from DER, 989' to 1139' right of centerline, 0' AGL/339' MSL up to 349' MSL. Aircraft parked 42' from DER, 544' right of centerline, 0' AGL/255' MSL. Pylon 2668' from DER, 1714' right of centerline, 79' AGL/286' MSL. **Rwy 23**, Multiple trees left of centerline, beginning 2482' out to 3574' from DER, 186' to 1423' left of centerline, 130' AGL/351' MSL up to 363' MSL. Wind sensor 500' from DER, 495' left of centerline, 33' AGL/275' MSL. Multiple trees right of centerline, beginning 2470' out to 3968' from DER, 419' to 1200' right of centerline, 0' AGL/343' MSL up to 367' MSL. Light pole 2172' from DER, 615' to 791' right of centerline, 26' AGL/274' MSL. **Rwy 32**, Multiple trees left of centerline, beginning 2267' out to 5053' from DER, 68' to 1650' left of centerline, 0' AGL/335' MSL up to 381' MSL. Multiple trees right of centerline, beginning 1774' out to 2207' from DER, 475' to 820' right of centerline, 0' AGL/343' MSL up to 355' MSL.

MOCKSVILLE, NC

TWIN LAKES (8A7)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 07214 (FAA)

TAKEOFF MINIMUMS: **Rwy 27**, 300-1
TAKEOFF OBSTACLE NOTES: **Rwy 9**, numerous trees beginning 35' from DER, 27' right of centerline, up to 100' AGL/939' MSL. Numerous trees beginning 200' from DER, 164' left of centerline, up to 100' AGL/919' MSL. **Rwy 27**, numerous trees beginning 200' from DER, 78' right of centerline, up to 100' AGL/ 929' MSL. Numerous trees beginning 616' from DER, 77' left of centerline, up to 100' AGL/909' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

MONCKS CORNER, SC

BERKELEY COUNTY (MKS)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 09015 (FAA)

TAKEOFF MINIMUMS: **Rwy 5**, 300-1¼ or std. w/ min. climb of 215' per NM to 400.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 17' from DER, 102' right of centerline, up to 99' AGL/158' MSL. Terrain 30' from DER, 478' left of centerline, 79' MSL. Trees beginning 964' from DER, 66' left of centerline, up to 108' AGL/167' MSL. Poles beginning 467' from DER, 480' left of centerline, up to 24' AGL/103' MSL. Tower 1.4 NM from DER, 530' left of centerline, up to 228' AGL/292' MSL. **Rwy 23**, trees beginning abeam DER, 361' right of centerline, up to 100' AGL/199' MSL. Transmission poles beginning 1320' from DER, 249' right of centerline, up to 63' AGL/142' MSL. Terrain 21' from DER, 125' left of centerline, 76' MSL. Trees beginning 1141' from DER, 47' left of centerline, up to 84' AGL/163' MSL. Transmission pole 2503' from DER, 115' left of centerline, 62' AGL/141' MSL.

MONROE, NC

CHARLOTTE-MONROE EXECUTIVE (EQY)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 15232 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 24' from DER, 308' right of centerline, up to 77' AGL/736' MSL. Trees beginning 70' from DER, 218' left of centerline, up to 27' AGL/686' MSL. Trees beginning 606' from DER, 58' right of centerline, up to 33' AGL/692' MSL. Poles and trees beginning 651' from DER, 19' left of centerline, up to 44' AGL/713' MSL. Trees beginning 1223' from DER, 436' right of centerline, up to 62' AGL/721' MSL. Trees beginning 2151' from DER, 79' left of centerline, up to 89' AGL/748' MSL. **Rwy 23**, runway light 12' from DER, 31' left of centerline, 2' AGL/684' MSL. Trees beginning 1714' from DER, 203' left of centerline, up to 97' AGL/746' MSL. Trees 2366' from DER, 771' right of centerline, up to 86' AGL/755' MSL.

MOORESVILLE, NC

LAKE NORMAN AIRPARK (14A)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 06327 (FAA)

TAKEOFF MINIMUMS: **Rwy 14**, std. w/ a min. climb of 294' per NM to 2900 or 1300-2½ for climb in visual conditions.

DEPARTURE PROCEDURE: **Rwy 14**, for climb in visual conditions: cross Lake Norman Airport at or above 2000' MSL before proceeding on course. **Rwy 32**, climb heading 324° to 1300 before proceeding on course.

TAKEOFF OBSTACLE NOTES: **Rwy 14**, terrain and multiple trees beginning 197' from DER, 308' left of centerline, up to 200' AGL/1099' MSL. Building and multiple trees beginning 158' from DER, 258' right of centerline, up to 100' AGL/979' MSL. **Rwy 32**, tree 559' from DER, on centerline, 42' AGL/851' MSL. Multiple trees beginning 47' from DER, 34' left of centerline, up to 101' AGL/890' MSL. Multiple trees beginning 526' from DER, 31' right of centerline, up to 97' AGL/886' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

MORGANTON, NC

FOOTHILLS RGNL (MRN)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 11181 (FAA)

TAKEOFF MINIMUMS: **Rwy 21**, std. w/min. climb of 225' per NM to 3800.

DEPARTURE PROCEDURE: **Rwy 3**, climbing left turn direct FIQ NDB, thence ...

Rwy 21, climb direct FIQ NDB, thence ...

... continue climbing in holding pattern (Southwest, left turns, 031° inbound) to 5000 before proceeding on course.

TAKEOFF OBSTACLE NOTES: **Rwy 3**, trees beginning 167' from DER, 388' right of centerline, up to 100' AGL/1379' MSL. Rising terrain beginning 138' from DER, 3' right of centerline, up to 1280' MSL. Trees beginning 1180' from DER, 421' left of centerline, up to 68' AGL/1327' MSL. Rising terrain beginning 39' from DER, 223' left of centerline, up to 1277' MSL. **Rwy 21**, trees beginning 2329' from DER, 1061' right of centerline, up to 100' AGL/1339' MSL. Trees beginning 1681' from DER, 883' left of centerline, up to 100' AGL/1379' MSL.

MOUNT AIRY, NC

MOUNT AIRY/SURRY COUNTY (MWK)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 3 14037 (FAA)

TAKEOFF MINIMUMS: **Rwy 36**, std. w/min. climb of 250' per NM to 3900, or 2300-3 for climb in visual conditions. DEPARTURE PROCEDURE: **Rwy 18**, climb heading 180° to 3000 before turning left. **Rwy 36**, Climb on heading 360° to intercept PSK R-173 to PSK VORTAC before proceeding on course or for climb in visual conditions: cross Mount Airy/Surry County airport at or above 3400 MSL before proceeding on course. When executing VCOA, notify ATC prior to departure.

TAKEOFF OBSTACLE NOTES: **Rwy 18**, vehicles on roadway beginning 102' from DER, 462' right of centerline, up to 17' AGL/1236' MSL. Trees beginning 67' from DER, 494' left of centerline, up to 70' AGL/1279' MSL. Trees beginning 594' from DER, 658' right of centerline, up to 50' AGL/1257' MSL. Building 1842' from DER, 96' left of centerline, 47' AGL/1260' MSL. Trees beginning 2717' from DER, left and right of centerline, up to 82' AGL/1300' MSL. Trees beginning 3500' from DER, 626' left of centerline, up to 100' AGL/1339' MSL. **Rwy 36**, rising terrain beginning 40' from DER, left and right of centerline, up to 1364' MSL. Power pole 408' from DER, 248' left of centerline, 40' AGL/1315' MSL. Vehicles on roadway beginning 98' from DER, left and right of centerline, up to 15' AGL/1334' MSL. Trees beginning 1089' from DER, left and right of centerline, up to 100' AGL/1399' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

MOUNT OLIVE, NC

MOUNT OLIVE MUNI (W40)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 13066 (FAA)

TAKEOFF MINIMUMS: **Rwy 23**, 300-1 or std. w/ min. climb of 334' per NM to 500.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 971' from DER, 27' left of centerline, up to 100' AGL/267' MSL. Trees beginning 2209' from DER, 25' right of centerline, up to 100' AGL/262' MSL. Pole 454' from DER, 407' left of centerline, 17' AGL/191' MSL. Vehicle on road 363' from DER, 115' left of centerline, 15' AGL/179' MSL. Vehicle on road 321' from DER, 106' right of centerline, 15' AGL/181' MSL. GND 14' from DER, 107' right of centerline, 167' MSL. **Rwy 23**, tower 4535' from DER, 445' right of centerline, 196' AGL/355' MSL. Trees beginning 185' from DER, 108' left of centerline, up to 100' AGL/253' MSL. Trees beginning 865' from DER, 226' right of centerline, up to 100' AGL/259' MSL. Buildings beginning 110' from DER, 323' left of centerline, up to 25' AGL/181' MSL. Poles beginning 279' from DER, 43' left of centerline, up to 20' AGL/184' MSL.

MOUNT PLEASANT, SC

MT PLEASANT RGNL-FAISON FIELD
(LRO)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 10126 (FAA)

DEPARTURE PROCEDURE: **Rwy 17**, climb heading 174° to 1400 before proceeding on course. **Rwy 35**, climb heading 354° to 1900 before turning right.
TAKEOFF OBSTACLE NOTES: **Rwy 17**, AAO 3.8 NM from DER, 4834' right of centerline, 200' AGL/210' MSL. **Rwy 35**, tree 1900' from DER, 921' left of centerline, 84' AGL/96' MSL. Tree 3043' from DER, 401' right of centerline, 83' AGL/95' MSL.

MYRTLE BEACH, SC

MYRTLE BEACH INTL (MYR)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 10042 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 18**, trees beginning 1770' from DER, 664' left of centerline, up to 60' AGL/88' MSL.

NEW BERN, NC

COASTAL CAROLINA RGNL (EWN)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 4 12320 (FAA)

TAKEOFF MINIMUMS: **Rwy 14**, 300-1 or std. w/ min. climb of 240' per NM to 300, or alternatively, with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1900' prior to DER. **Rwy 32**, std. w/ min. climb of 215' per NM to 800, or 1100-2/2 for climb in visual conditions.
DEPARTURE PROCEDURE: **Rwy 4**, climb heading 039° to 600 before turning north. **Rwy 32**, climb heading 316° to 800 before turning north, or for climb in visual conditions cross coastal Carolina RGNL airport at or above 1000 MSL before proceeding on course. When executing VCOA, notify ATC prior to departure.

TAKEOFF OBSTACLE NOTES: **Rwy 4**, signs beginning 9' from DER, 429' right of centerline, up to 45' AGL/61' MSL. Vehicles on road beginning 87' from DER, 499' left of centerline, up to 17' AGL/27' MSL. Trees, sign and vertical structure beginning 648' from DER, left and right of centerline, up to 91' AGL/104' MSL. **Rwy 14**, trees beginning 92' from DER, 257' left of centerline, up to 77' AGL/92' MSL. Trees and pole beginning 226' from DER, 146' right of centerline, up to 98' AGL/118' MSL. Trees and tower beginning 3335' from DER, 118' left of centerline, up to 120' AGL/145' MSL. Antenna 5034' from DER, 1239' left of centerline, up to 147' AGL/170' MSL. **Rwy 22**, bush beginning 101' from DER, 288' left of centerline, up to 6' AGL/16' MSL. Trees beginning 803' from DER, 56' left of centerline, up to 115' AGL/116' MSL. Trees beginning 809' from DER, 87' right of centerline, up to 134' AGL/139' MSL. Trees beginning 2977' from DER, left and right of centerline, up to 115' AGL/122' MSL. **Rwy 32**, bush and trees beginning 141' from DER, 236' left of centerline, up to 68' AGL/78' MSL. Trees beginning 718' from DER, right of centerline, up to 101' AGL/111' MSL. Trees and transmission tower 744' from DER, 31' left of centerline, up to 116' AGL/126' MSL.

NEWBERRY, SC

NEWBERRY COUNTY (EOE)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 08325 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 4**, multiple trees beginning 1895' from DER, left and right of centerline, up to 100' AGL/659' MSL. **Rwy 22**, multiple trees beginning 500' from DER, left and right of centerline, up to 100' AGL/629' MSL.

NEW RIVER MCAS (MC CUTCHEON FLD) (KNCA)

JACKSONVILLE, NC
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 17173

TAKEOFF OBSTACLE NOTES: **Rwy 1**, building 1375' from DER, 1119' left of cntrln, 80' AGL/96' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

NORTH AF AUX (KXNO)

NORTH, SC

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

ORIG 17061

CAUTION: **Rwy 5/23** diverse departure procedures not authorized at night.

TAKEOFF OBSTACLE NOTES: **Rwy 6**, possible C-5 on taxiway B, 687' from DER, 535' right of centerline, 65' AGL/ 386' MSL. Pylon 2363' from DER, 1572' left of centerline, 79' AGL/403' MSL. Multiple towers 2450' to 2821' from DER, 922' to 1127' left of centerline, 53' AGL/381' MSL. Trees 1409' to 3007' from DER, 162' to 1002' left of centerline, 104' AGL/408' MSL. **Rwy 24**, pylon 1729' from DER, 1456' right of centerline, 79' AGL/325' MSL. Trees 1092' to 2049' from DER, 344' to 885' right of centerline, 91' AGL/335' MSL.

NORTH MYRTLE BEACH, SC

GRAND STAND (CRE)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

ORIG 10014 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, vehicles on roadway 8' from DER, 455' right of centerline, up to 16' AGL/41' MSL. Trees beginning 1782' from DER, 6' right of centerline, up to 74' AGL/103' MSL. **Rwy 23**, trees beginning 43' from DER, 399' right of centerline, up to 33' AGL/58' MSL. Sign 60' from DER, 205' left of centerline, 11' AGL/36' MSL. Trees beginning 1393' from DER, 277' left of centerline, up to 62' AGL/88' MSL.

NORTH WILKESBORO, NC

WILKES COUNTY (UKF)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 1 17229 (FAA)

TAKEOFF MINIMUMS: **Rwy 1**, std. w/min. climb of 330' per NM to 5000 or 2000-3 for climb in visual conditions.**Rwy 19**, std. w/min. climb of 230' per NM to 3200 or 2000-3 for climb in visual conditions.DEPARTURE PROCEDURE: **Rwy 19**, climb heading 187° to 3200 before proceeding on course.

VCOA: Obtain ATC approval for VCOA when requesting IFR clearance. climb in visual conditions to cross Wilkes County airport at or above 3200 before proceeding on course.

TAKEOFF OBSTACLE NOTES: **Rwy 1**, trees, terrain beginning 2' from DER, 309' right of centerline, up to 1344' MSL. Tree 44' from DER, 447' left of centerline, 1351' MSL. Trees, terrain beginning 65' from DER, 89' left of centerline, up to 1352' MSL. Trees beginning 171' from DER, 495' left of centerline, up to 1364' MSL. Trees, terrain beginning 294' from DER, 81' left of centerline, up to 1367' MSL. Trees and vertical structure beginning 324' from DER, 263' right of centerline, up to 1358' MSL. Trees, terrain beginning 425' from DER, 163' right of centerline, up to 1367' MSL. Tree 484' from DER, 491' right of centerline, 1378' MSL. Trees, terrain beginning 520' from DER, 262' right of centerline, up to 1379' MSL. Tree and pole beginning 587' from DER, 188' left of centerline, up to 1370' MSL. Trees beginning 760' from DER, 263' right of centerline, up to 1381' MSL. Trees beginning 1014' from DER, 146' right of centerline, up to 1389' MSL. Tree 1417' from DER, 537' left of centerline, 1374' MSL. Tree 1452' from DER, 641' left of centerline, 1384' MSL. Trees beginning 1528' from DER, 1' left of centerline, up to 1403' MSL. Tree and pole beginning 2154' from DER, 423' left of centerline, up to 1421' MSL. Tree, pole beginning 2369' from DER, 357' left of centerline, up to 1423' MSL. Trees beginning 2784' from DER, 497' right of centerline, up to 1393' MSL. Trees beginning 3436' from DER, 726' right of centerline, up to 1406' MSL. Trees beginning 3646' from DER, 1115' right of centerline, up to 1413' MSL. Tree 4982' from DER, 1807' left of centerline, 1428' MSL. Trees beginning 5360' from DER, 187' right of centerline, up to 1443' MSL. Tree 5510' from DER, 363' right of centerline, 1448' MSL. Trees beginning 5544' from DER, 290' right of centerline, up to 1460' MSL. **Rwy 19**, tree 21' from DER, 484' right of centerline, 100' AGL/1328' MSL. Trees beginning 26' from DER, on centerline, up to 100' AGL/1347' MSL. Trees beginning 32' from DER, 6' left of centerline, up to 100' AGL/1357' MSL.

OAK ISLAND, NC

CAPE FEAR RGNL JETPORT / HOWIE

FRANKLIN FLD (SUT)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 1 12180 (FAA)

TAKEOFF MINIMUMS: **Rwy 5**, 400-3 or std. w/min. climb of 210' per NM to 600, or alternatively with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1500' prior to DER.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, building, trees and towers beginning 18' from DER, 21' right of centerline, up to 92' AGL/97' MSL. Trees beginning 257' from DER, 21' left of centerline, up to 89' AGL/104' MSL. **Rwy 23**, trees beginning 42' from DER, left and right of centerline, up to 92' AGL/102' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)


**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**


17229

ORANGEBURG, SC

ORANGEBURG MUNI (OGB)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 3A 10126 (FAA)

DEPARTURE PROCEDURE: **Rwy 5**, climb heading 049° to 1000 before proceeding on course. **Rwy 35**, climb heading 354° to 900 before proceeding on course.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 190' from DER, 384' left of centerline, up to 100' AGL/289' MSL. Railroad 768' from DER, 407' right of centerline, 23' AGL/220' MSL. **Rwy 17**, trees beginning 2885' from DER, 1082' left of centerline, up to 100' AGL/282' MSL. Trees beginning 1132' from DER, 798' right of centerline, up to 100' AGL/257' MSL. **Rwy 23**, trees beginning 32' from DER, 45' left of centerline, up to 100' AGL/251' MSL. Power pole 1260' from DER, 127' left of centerline, 50' AGL/202' MSL. Trees beginning 870' from DER, 419' right of centerline, up to 100' AGL/259' MSL. **Rwy 35**, trees beginning 764' from DER, 703' left of centerline, up to 100' AGL/272' MSL. Trees beginning 1567' from DER, 473' right of centerline, up to 100' AGL/282' MSL. Terrain 13' from DER, 34' right of centerline, 174' MSL.

OXFORD, NC

HENDERSON-OXFORD (HNZ)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 15064 (FAA)

DEPARTURE PROCEDURE: **Rwy 24**, climb heading 240° to 1300 before turning right.
TAKEOFF OBSTACLE NOTES: **Rwy 6**, trees beginning 263' from DER, 358' left of centerline, up to 68' AGL/558' MSL. Trees beginning 670' from DER, 496' right of centerline, up to 60' AGL/552' MSL. **Rwy 24**, silo, vehicles on road, telephone line, and trees beginning 7' from DER, 353' right of centerline, up to 88' AGL/601' MSL. Trees beginning 771' from DER, 10' left of centerline, up to 100' AGL/595' MSL. Trees beginning 1596' from DER, 248' left of centerline, up to 100' AGL/618' MSL.

PAGELAND, SC

PAGELAND (PYG)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 17061 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 6**, tree 10' from DER, 407' left of centerline, 601' MSL. Tree 38' from DER, 417' right of centerline, 582' MSL. Pole 67' from DER, 296' right of centerline, 595' MSL. Tree and pole beginning 73' from DER, 188' left of centerline, up to 607' MSL. Flag pole 81' from DER, 439' right of centerline, 596' MSL. Pole 114' from DER, 381' right of centerline, 597' MSL. Tree 199' from DER, 3277' right of centerline, 602' MSL. Trees beginning 222' from DER, 372' left of centerline, up to 608' MSL. Trees and vehicles on road beginning 265' from DER, 401' right of centerline, up to 621' MSL. Airport beacon, trees, and pole beginning 323' from DER, 102' right of centerline, up to 627' MSL. Trees, bldg, and poles beginning 324' from DER, 345' left of centerline, up to 622' MSL. Trees beginning 1235' from DER, 698' left of centerline, up to 630' MSL. Trees beginning 1295' from DER, 40' left of centerline, up to 641' MSL. Trees beginning 1793' from DER, 167' right of centerline, up to 635' MSL. Tree 2177' from DER, 36' left of centerline, 642' MSL. **Rwy 24**, tree 5' from DER, 287' right of centerline, 573' MSL. Tree 16' from DER, 378' right of centerline, 580' MSL. Tree and windsock beginning 20' from DER, 148' right of centerline, up to 581' MSL. Vehicle on road beginning 42' from DER, 406' left of centerline, up to 571' MSL. Tree and pole beginning 55' from DER, 390' left of centerline, up to 600' MSL. Trees beginning 111' from DER, 209' right of centerline, up to 587' MSL. Tree 138' from DER, 501' left of centerline, 604' MSL. Trees, fence, poles, bldg, and vehicles on road beginning 225' from DER, 417' left of centerline, up to 609' MSL. Trees beginning 1174' from DER, 364' left of centerline, up to 624' MSL.

PELION, SC

LEXINGTON COUNTY AT PELION (6J0)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 09155 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 18**, trees beginning 1705' from DER, 1' right of centerline, up to 71' AGL/521' MSL. Trees beginning 429' from DER, 298' left of centerline, up to 34' AGL/484' MSL. Power poles 430' from DER, 298' left of centerline, 33' AGL/484' MSL. **Rwy 36**, trees beginning 2016' from DER, 301' right of centerline, up to 59' AGL/511' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

17229


**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**


TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

PICKENS, SC

PICKENS COUNTY (LQK)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 09351 (FAA)

DEPARTURE PROCEDURE: **Rwy 5**, climb heading 048° to 2300 then climbing right turn via heading 120° to 3400 to intercept V20-35. **Rwy 23**, climb heading 228° to 2200 then climbing left turn via heading 120° to 3400 to intercept V20-35.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, tree 30' from DER, 299' left of centerline, 9' AGL/1022' MSL. Vehicles on roadway, 424' from DER, left and right of centerline, up to 15' AGL/1028' MSL. Trees beginning 1531' from DER, 691' left of centerline, up to 107' AGL/1038' MSL. Tree 3019' from DER, 450' right of centerline, 120' AGL/1095' MSL. **Rwy 23**, tree 906' from DER, 269' left of centerline, 91' AGL/990' MSL. Trees beginning 1015' from DER, 466' right of centerline, up to 106' AGL/1022' MSL.

PINEHURST/SOUTHERN PINES, NC MOORE COUNTY (SOP)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG-A 16231 (FAA)

DEPARTURE PROCEDURE: **Rwy 23**, climb heading 234° to 1100 before turning left.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, terrain 448' from DER, 343' right of centerline, 443' MSL. Trees beginning 663' from DER, 137' right of centerline, up to 100' AGL/475' MSL. Terrain 141' from DER, 329' left of centerline, 435' MSL. Trees beginning 176' from DER, 220' left of centerline, up to 100' AGL/529' MSL. **Rwy 23**, pipe 228' from DER, 431' right of centerline, 13' AGL/463' MSL. Antenna 657' from DER, 415' right of centerline, 32' AGL/482' MSL. Trees beginning 701' from DER, 422' right of centerline, up to 100' AGL/579' MSL. Trees beginning 364' from DER, 353' left of centerline, up to 100' AGL/569' MSL.

PLYMOUTH, NC

PLYMOUTH MUNI (PMZ)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 11349 (FAA)

TAKEOFF MINIMUMS: **Rwy 3**, 400-2 or std. w/min. climb of 270' per NM to 500.

DEPARTURE PROCEDURE: **Rwy 3**, climb heading 027° to 500 before turning left.

TAKEOFF OBSTACLE NOTES: **Rwy 3**, trees beginning 283' from DER, 55' left of centerline, up to 100' AGL/130' MSL. Trees beginning 109' from DER, 8' right of centerline, up to 100' AGL/130' MSL. Antenna 1.5 NM from DER, 3068' left of centerline, 347' AGL/366' MSL. **Rwy 21**, trees beginning 119' from DER, 8' left of centerline, up to 100' AGL/134' MSL. Trees beginning 123' from DER, 39' right of centerline, up to 100' AGL/134' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

POPE AAF (KPOB)

FORT BRAGG, NC
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 7 17145

DEPARTURE PROCEDURE:

Rwy 5: Expect radar vectors from Fayetteville Approach.

Rwy 23: Expect radar vectors from Fayetteville Approach. Standard with min climb of 232 ft/NM to 1000 or 300-1¾ with min climb of 220 ft/NM to 1000.

TAKEOFF OBSTACLE NOTES: **Rwy 5**, multiple trees 1473' to 1554' from DER, 776' right of centerline, up to 56' AGL/242' MSL. Multiple trees 2187' from DER, 1030' right of centerline, up to 80' AGL/265' MSL. Multiple trees 3388' from DER, 799' right of centerline, up to 103' AGL/276' MSL. Multiple trees 1682' from DER, 703' left of centerline, up to 57' AGL/231' MSL. Multiple trees 1980' to 3375' from DER, 922' left of centerline, up to 114' AGL/286' MSL.

Rwy 23, fence 1201' from DER, 71' left of centerline, 247' MSL. Terrain 1896' from DER, 864' right of centerline, 282' MSL. Terrain 1901' from DER, 1010' right of centerline, 268' MSL. Multiple trees 2322' to 2831' from DER, 710' right of centerline, up to 48' AGL/290' MSL. Multiple trees 2907' to 4488' from DER, 330' right of centerline, up to 82' AGL/347' MSL. Multiple ballpark lights 5098' from DER, 450' right of centerline, 75' AGL/348' MSL. Multiple trees 1278' to 1761' from DER, 266' left of centerline, up to 60' AGL/288' MSL. Multiple trees 3385' to 5885' from DER, 5' left of centerline, up to 75' AGL/368' MSL. Forestry tower 2.2 NM from DER, 3399' right of centerline, 140' AGL/559' MSL. Tree 1.4 NM from DER, 2527' left of centerline, 120' AGL/473' MSL. Trees 2542' to 2643' from DER, 128' left of centerline, 41' AGL/288' MSL. Possible C-5 976' from DER, 294' left of centerline, 65' AGL/274' MSL. Pylon and trees 1.3 NM from DER, 1285' left of centerline, 120' AGL/473' MSL. Tower 5900' from DER, 1750' right of centerline, 54' AGL/374' MSL. Tower 3.0 NM from DER, 1.4 NM right of centerline, 220' AGL/746' MSL.

RAEFORD, NC

P K AIRPARK (5W4)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 10322 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 4**, rising terrain 48' from DER, left and right of centerline, up to 332' MSL. Trees beginning 83' from DER, left and right of centerline, up to 100' AGL/429' MSL. Vehicles on road beginning 329' from DER, 189' right of centerline, up to 15' AGL/324' MSL. **Rwy 22**, terrain 42' from DER, left and right of centerline, up to 306' MSL. Trees beginning 268' from DER, left and right of centerline, up to 100' AGL/389' MSL. Vehicles on road beginning 1' from DER, left and right of centerline, up to 15' AGL/314' MSL.

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

RALEIGH-DURHAM, NC

RALEIGH-DURHAM INTL (RDU)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 6 10322 (FAA)

TAKEOFF MINIMUMS: **Rwy 32**, 300-1.
DEPARTURE PROCEDURE: **Rwy 14**, climb heading
142° to 1400 before turning right. **Rwy 23L**, climb
heading 232° to 1900 before turning left. **Rwy 23R**,
climb heading 232° to 1800 before turning left.

TAKEOFF OBSTACLE NOTES: **Rwy 5L**, trees 3802'
from DER, 1237' left of centerline, up to 77' AGL/506'
MSL. Tank and trees beginning 2011' from DER, 948'
right of centerline, up to 138' AGL/547' MSL. **Rwy 5R**,
trees 1436' from DER, 803' right of centerline, up to 80'
AGL/469' MSL. **Rwy 14**, trees beginning 2021' from
DER, 510' left of centerline, up to 116' AGL/545' MSL.
Trees beginning 2467' from DER, 2' right of centerline,
up to 122' AGL/571' MSL. **Rwy 23L**, trees 1495' from
DER, 797' left of centerline, up to 58' AGL/447' MSL.
Light pole 1457' from DER, 878' right of centerline, 93'
AGL/452' MSL. **Rwy 32**, light poles beginning 1170'
from DER, 618' left of centerline, up to 55' AGL/486'
MSL. Hangar 1242' from DER, 753' right of centerline,
34' AGL/473' MSL. Control tower 2207' from DER, 910'
right of centerline, 231' AGL/660' MSL.

DIVERSE VECTOR AREA (RADAR VECTORS)

AMDT 1 17173 (FAA)

Rwy 14, heading as assigned by ATC; requires
minimum climb of 310' per NM to 1000. **Rwy 23L**,
heading as assigned by ATC; requires minimum climb
of 250' per NM to 2300. **Rwy 23R**, heading as
assigned by ATC; requires minimum climb of 240' per
NM to 2100.

REIDSVILLE, NC

ROCKINGHAM COUNTY NC SHILOH (SIF)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 09295 (FAA)

TAKEOFF MINIMUMS: **Rwy 31**, 400-2 or std. w/ a min.
climb of 535' per NM to 1200.

TAKEOFF OBSTACLE NOTES: **Rwy 13**, trees
beginning 40' from DER, 63' left of centerline, up to
100' AGL/768' MSL. Power pole 1192' from DER, 430'
right of centerline, 30' AGL/702' MSL. Tree beginning
1539' from DER, 30' right of centerline, up to 100'
AGL/755' MSL. **Rwy 31**, power pole 2054' from DER,
243' right of centerline, 30' AGL/763' MSL. Vehicle on
road 31' from DER, 485' left of centerline, 15' AGL/714'
MSL. Trees beginning 1164' from DER, 187' right of
centerline, up to 100' AGL/1019' MSL. Trees beginning
152' from DER, 317' left of centerline, up to 100'
AGL/979' MSL. Rising terrain beginning 123' from
DER, 27' left of centerline, up to 939' MSL. Rising
terrain beginning 64' from DER, 27' right of centerline,
up to 939' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

ROANOKE RAPIDS, NC

HALIFAX-NORTHAMPTON RGNL (IXA)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 1 17229 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 20**, tree 100' from
DER, 492' left of centerline, 178' MSL. Tree 1363' from
DER, 183' right of centerline, 182' MSL. Trees beginning
1420' from DER, 27' right of centerline, up to 187' MSL.
Tree 1515' from DER, 29' left of centerline, 179' MSL.
Tree 1696' from DER, 56' left of centerline, 191' MSL.
Tree 1724' from DER, 127' left of centerline, 195' MSL.
Trees beginning 1780' from DER, 70' left of centerline,
up to 199' MSL. Trees beginning 2026' from DER, 151'
left of centerline, up to 200' MSL. Tree 2276' from DER,
77' right of centerline, 199' MSL. **Rwy 02**, NAVAID 39'
from DER, 125' right of centerline, 20' AGL/140' MSL.
NAVAID 40' from DER, 124' left of centerline, 18'
AGL/141' MSL. Tree 1298' from DER, 722' right of
centerline, 183' MSL.

ROCK HILL, SC

ROCK HILL/YORK COUNTY/BRYANT FIELD
(UZA)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 15232 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 2**, trees beginning
99' from DER, 491' right of centerline, up to 89' AGL/750'
MSL. Trees beginning 1857' from DER, 77' right of
centerline, up to 101' AGL/730' MSL. Trees beginning
2096' from DER, 3' left of centerline, up to 84' AGL/723'
MSL. **Rwy 20**, vegetation 153' from DER, 470' right of
centerline, up to 8' AGL/673' MSL. Trees 3231' from
DER, 40' left of centerline, up to 83' AGL/749' MSL.

ROCKINGHAM, NC

RICHMOND COUNTY (RCZ)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 10154 (FAA)

TAKEOFF MINIMUMS: **Rwys 4, 22**, NA-Environmental.
TAKEOFF OBSTACLE NOTES: **Rwy 14**, multiple trees
beginning 676' from DER, 20' right of centerline, up to
100' AGL/441' MSL. Multiple trees beginning 5' from
DER, 75' left of centerline, up to 100' AGL/458' MSL.
Train beginning 6' from DER, 355' left of centerline, 23'
AGL/382' MSL. **Rwy 32**, tree 1152' from DER, 443' left
of centerline, 100' AGL/399' MSL. Tree 181' from DER,
428' right of centerline, 100' AGL/429' MSL. Vehicles on
roadway 34' from DER, 498' right of centerline, up to 15'
AGL/364' MSL.

ROCKY MOUNT, NC

ROCKY MOUNT-WILSON RGNL (RWI)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2 12096 (FAA)

DEPARTURE PROCEDURE: **Rwy 22**, climb heading 222°
to 1200 before turning right.
TAKEOFF OBSTACLE NOTES: **Rwy 4**, trees 1457' from
DER, 792' left of centerline, up to 58' AGL/207' MSL.
Trees 2452' from DER, 751' right of centerline, up to 72'
AGL/231' MSL. **Rwy 22**, trees beginning 1215' from
DER, 428' left of centerline, up to 66' AGL/224' MSL.
Trees 2452' from DER, 665' right of centerline, up to 45'
AGL/204' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**

17229

ROXBORO, NC

PERSON COUNTY (TDF)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 06215 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 6**, trees 1600' from DER, 200' right of centerline, 100' AGL/729' MSL. **Rwy 24**, trees 562' from DER, 577' left of centerline, 100' AGL/699' MSL.

RUTHERFORDTON, NC

RUTHERFORD CO-MARCHMAN FIELD
(FQD)

TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 3 15148 (FAA)

TAKEOFF MINIMUMS: **Rwy 1**, std. w/min. climb of 220' per NM to 2600 or 2900-3 for climb in visual conditions. **Rwy 19**, std. w/min. climb of 205' per NM to 3100 or 2900-3 for climb in visual conditions.

DEPARTURE PROCEDURE: **Rwy 1**, Climbing right turn heading 130° to intercept 200° course to FRT NDB. ADF required. **Rwy 19**: Climb heading 189° to 3100 before proceeding on course.

VCOA: Obtain ATC approval for climb in visual conditions when requesting IFR clearance. Climb in visual conditions to cross Rutherford Co-Marchman Field at or above 3800 before proceeding on course.

TAKEOFF OBSTACLE NOTES: **Rwy 1**: tree 6' from DER, 377' left of centerline, 80' AGL/1139' MSL. NAVAID 174' from DER, 250' left of centerline, 25' AGL/1088' MSL. Tree 315' from DER, 478' right of centerline, 52' AGL/1151' MSL. Tree 862' from DER, 50' right of centerline, 100' AGL/1139' MSL. Tree 1985' from DER, 988' right of centerline, 67' AGL/1166' MSL. Tree 2107' from DER, 318' right of centerline, 100' AGL/1219' MSL. Tree 3250' from DER, 825' right of centerline, 100' AGL/1219' MSL. **Rwy 19**: tree 28' from DER, 329' left of centerline, 60' AGL/1080' MSL. Tree 259' from DER, 500' right of centerline, 100' AGL/1139' MSL. Tree 489' from DER, 455' right of centerline, 26' AGL/1088' MSL. Tree 2358' from DER, 200' left of centerline, 100' AGL/1139' MSL.

ST. GEORGE, SC

ST. GEORGE (6J2)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 08101 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, tree 3021' from DER, 186' left of centerline, 100' AGL/175' MSL.

Rwy 23, tree 1401' from DER, 259' right of centerline, 100' AGL/178' MSL.

SALISBURY, NC

ROWAN COUNTY (RUQ)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
AMDT 2A 17229 (FAA)

TAKEOFF MINIMUMS: **Rwy 20**, 400-2% or std. w/min. climb of 205' per NM to 1300, or alternatively, with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1200' prior to DER.

DEPARTURE PROCEDURE: **Rwy 20**, climb heading 202° to 1700 before turning right.

TAKEOFF OBSTACLE NOTES: **Rwy 2**, trees beginning 106' from DER, 474' right of centerline, up to 68' AGL/787' MSL.

Rwy 20, trees beginning 167' from DER, 483' right of centerline, up to 31' AGL/810' MSL. Building and trees beginning 668' from DER, 275' left of centerline, up to 40' AGL/809' MSL. Trees beginning 890' from DER, 59' right of centerline, up to 43' AGL/822' MSL. Trees beginning 1055' from DER, 476' right of centerline, up to 112' AGL/871' MSL. Trees beginning 2251' from DER, 3' left of centerline, up to 97' AGL/896' MSL. Trees beginning 2410' from DER, 17' right of centerline, up to 114' AGL/913' MSL. Tower 2.3 NM from DER, 2196' right of centerline, 306' AGL/1121' MSL.

SALUDA, SC

SALUDA COUNTY (6J4)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES
ORIG 09351 (FAA)

TAKEOFF MINIMUMS: **Rwy 19**, 300-2 or std. w/ min. climb of 207' per NM to 900, or alternatively, with standard takeoff minimums and a normal 200'/NM climb gradient, takeoff must occur no later than 1400' prior to DER.

TAKEOFF OBSTACLE NOTES: **Rwy 1**, numerous trees beginning abeam DER, 40' left of centerline, up to 66' AGL/635' MSL. Numerous trees beginning abeam DER, 35' right of centerline, up to 100' AGL/649' MSL. **Rwy 19**, numerous trees beginning abeam DER, 20' left of centerline, up to 43' AGL/552' MSL. Numerous trees beginning abeam DER, 30' right of centerline, up to 100' AGL/639' MSL.

SANFORD, NC

RALEIGH EXEC JETPORT AT SANFORD-
LEE COUNTY (TTA)
TAKEOFF MINIMUMS AND (OBSTACLE)
DEPARTURE PROCEDURES

AMDT 1 11237 (FAA)

DEPARTURE PROCEDURE: **Rwy 3**, climb heading 029° to 1100 before turning right. **Rwy 21**, climb heading 209° to 1500 before turning left.

TAKEOFF OBSTACLE NOTES: **Rwy 3**, trees beginning 3313' from DER, 380' right of centerline, up to 89' AGL/318' MSL. **Rwy 21**, trees beginning 89' from DER, 435' right of centerline, up to 29' AGL/259' MSL.

17229

**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

SEYMOUR JOHNSON AFB (KGSB) GOLDSBORO, NC TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES AMDT 2, 14205

TAKEOFF MINIMUMS: **Rwy 26**, 200-1½ or standard with minimum climb of 210 ft/NM to 500' or with standard minimums and a standard 200 ft/NM climb gradient, takeoff must occur no later than 1300' prior to DER.

TAKEOFF OBSTACLE NOTES: **Rwy 8**, vehicle, 15' AGL/128' MSL, 1547' from DER, 796' right of centerline. Multiple trees, 80' AGL/194' MSL, beginning 3014' from DER, 952' left of centerline. **Rwy 26**, trees 110' AGL/235' MSL, 1.2 NM from DER, 1155' left of centerline.

SHAW AFB (KSSC) SUMTER, SC TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES ORIG, 14289

TAKEOFF OBSTACLE NOTES: **Rwy 4R**, terrain 500' left of centerline, at the threshold, 236' MSL. Surveyed terrain 500' left of centerline, 234' MSL. **Rwy 22L**, radio tower 5137' from DER, 1701' left of centerline, 140' AGL/369' MSL. Glideslope antenna 563' from DER, 500' right of centerline, 40' AGL/273' MSL. Terrain 0' inward of DER, 500' right of centerline, 236' MSL. **Rwy 22R**, terrain beginning at 255' from DER, 500' right of centerline to 568' right of centerline, up to 246' MSL. Trees 4651' from DER, 832' right of centerline, 65' AGL/337' MSL.

SHELBY, NC SHELBY-CLEVELAND COUNTY RGNL (EHO) TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES ORIG 09015 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 74' from DER, 394' left of centerline, up to 99' AGL/899' MSL. Trees beginning 2018' from DER, 804' right of centerline, up to 100' AGL/919' MSL.

Rwy 23, trees beginning 186' from DER, 148' left of centerline, up to 93' AGL/903' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

L24

SILER CITY, NC SILER CITY MUNI (SCR) TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES AMDT 2 15008 (FAA)

TAKEOFF MINIMUMS: **Rwy 4**, 300-1¼ or std. w/min. climb of 236' per NM to 1000 or alternatively, with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 2000' prior to DER.

TAKEOFF OBSTACLE NOTES: **Rwy 4**, trees beginning 25' from DER, 25' right of centerline, up to 96' AGL/855' MSL. Poles beginning 158' from DER, 364' left of centerline, up to 34' AGL/643' MSL. Trees beginning 275' from DER, 3' left of centerline, up to 96' AGL/825' MSL. **Rwy 22**, trees beginning 8' from DER, 3' left of centerline, up to 77' AGL/736' MSL. Vehicles on road beginning 86' from DER, 330' right of centerline, up to 15' AGL/612' MSL. Trees beginning 154' from DER, 5' right of centerline, up to 100' AGL/749' MSL. Bldg 374' from DER, 466' right of centerline, 20' AGL/619' MSL. Pole 490' from DER, 357' right of centerline, 26' AGL/625' MSL. Pole 580' from DER, 481' right of centerline, 18' AGL/617' MSL. Bldg 591' from DER. 427' right of centerline, 16' AGL/615' MSL. Pole 769' from DER, 314' right of centerline, 19' AGL/618' MSL. Pole 1188' from DER, 253' right of centerline, 23' AGL/632' MSL.

SIMMONS AAF (KFBG) FORT BRAGG, NC TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES AMDT 2A, 13010

Rwy 27, 400-2½*

* Or standard with minimum climb of 230 ft/NM to 700.

DEPARTURE PROCEDURE: **Rwy 27**, climb heading 273° to 800 before proceeding on course.

TAKEOFF OBSTACLE NOTES: **Rwy 9**, Terrain 233' MSL, beginning 80' from DER, 27' right of centerline. **Rwy 27**, Terrain 283' MSL, beginning 105' from DER, left and right of centerline. Antenna, 292' AGL/584' MSL, 1.9 NM from DER, 3586' right of centerline.

SMITHFIELD, NC JOHNSTON RGNL (JNX) TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES AMDT 4 15120 (FAA)

TAKEOFF MINIMUMS: **Rwy 3**, 300-1½ or std. w/ min climb of 265' per NM to 500. **Rwy 21**, 500-2¼ or std. w/ min climb of 265' per NM to 800.

DEPARTURE PROCEDURE: **Rwy 3**, climb heading 032° to 1500 before turning left. **Rwy 21**, climb heading 212° to 1000 before turning right.

TAKEOFF OBSTACLE NOTES: **Rwy 3**, trees beginning 35' from DER, 380' right of centerline, up to 96' AGL/276' MSL. Terrain 99' from DER, 364' right of centerline, 171' MSL. Poles beginning 1236' from DER, 30' left and right of centerline, up to 44' AGL/234' MSL. Trees beginning 2317' from DER, 103' left of centerline, up to 100' AGL/349' MSL. Building 2610' from DER, 244' left of centerline, 36' AGL/231' MSL. Tank 2732' from DER, 6' left of centerline, 45' AGL/238' MSL. Tree 1 NM from DER, 251' right of centerline, 131' AGL/301' MSL. **Rwy 21**, trees beginning 1' from DER, 338' right of centerline, up to 100' AGL/269' MSL. Trees beginning 21' from DER, 366' left of centerline, up to 62' AGL/232' MSL. Terrain 1374' from DER, 589' left of centerline, 187' MSL. Pole 1409' from DER, 816' left of centerline, 27' AGL/210' MSL. Tower 2.6 NM from DER, 2887' right of centerline, 378' AGL/613' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

SE-2

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

17229

SPARTANBURG, SC

SPARTANBURG DOWNTOWN

MEMORIAL (SPA)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1A 15288 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees 189' from DER, 402' right of centerline, up to 31' AGL/832' MSL. Trees 1260' from DER, 660' left of centerline, up to 70' AGL/837' MSL. **Rwy 23**, terrain 10' from DER, on centerline, up to 793' MSL. Trees 136' from DER, 451' left of centerline, up to 67' AGL/825' MSL. Trees beginning 3390' from DER, 301' right of centerline, up to 93' AGL/901' MSL. Trees 3476' from DER, 208' left of centerline, up to 87' AGL/884' MSL.

STAR, NC

MONTGOMERY COUNTY (43A)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 14261 (FAA)

TAKEOFF MINIMUMS: **Rwy 3**, 300-1¼ or std. w/min. climb of 205' per NM to 900, or alternatively, with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1200' prior to DER. **Rwy 21**, 300-1¼ or std. w/min. climb of 238' per NM to 800, or alternatively, with standard takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1900' prior to DER.

TAKEOFF OBSTACLE NOTES: **Rwy 3**, tank 6188' from DER, 1619' left of centerline, 145' AGL/793' MSL. Trees beginning 7' from DER, 169' left of centerline, up to 100' AGL/739' MSL. Trees beginning 250' from DER, 334' right of centerline, up to 100' AGL/739' MSL. Power line beginning 123' from DER, 38' right of centerline, 40' AGL/670' MSL. **Rwy 21**, trees beginning 184' from DER, 407' left of centerline, up to 100' AGL/729' MSL. Trees beginning 24' from DER, 259' right of centerline, up to 100' AGL/719' MSL.

STATESVILLE, NC

STATESVILLE RGNL (SVH)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 05300 (FAA)

TAKEOFF MINIMUMS: **Rwy 28**, 300-1¼ or std. with a min. climb of 220' per NM to 1300.

TAKEOFF OBSTACLE NOTES: **Rwy 28**, power line tower 8880' from DER, 858' right of centerline, 180' AGL/1199' MSL.

SUMMERVILLE, SC

SUMMERVILLE (DYB)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 10210 (FAA)

DEPARTURE PROCEDURE: **Rwy 6**, climb heading 056° to 600 before turning left. **Rwy 24**, climb heading 236° to 800 before turning right.

TAKEOFF OBSTACLE NOTES: **Rwy 6**, vehicles on road beginning 7' from DER, left and right of centerline, up to 15' AGL/64' MSL. Trees beginning 556' from DER, left and right of centerline, up to 100' AGL/154' MSL. **Rwy 24**, tree 58' from DER, 459' left of centerline, 84' AGL/114' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

SUMTER, SC

SUMTER (SMS)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 09295 (FAA)

TAKEOFF MINIMUMS: **Rwys 14, 32**, NA-VFR only. **Rwy 23**, std. w/ a min. climb of 221' per NM to 800 or 900-2½ for climb in visual conditions.

DEPARTURE PROCEDURE: **Rwy 23**, for climb in visual conditions: cross Sumter airport at or above 900 MSL before proceeding on course.

TAKEOFF OBSTACLE NOTES: **Rwy 23**, trees beginning 2876' from DER, 559' left of centerline, up to 72' AGL/251' MSL. Trees beginning 117' from DER, 210' right of centerline, up to 86' AGL/265' MSL.

SYLVA, NC

JACKSON COUNTY (24A)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 15008 (FAA)

TAKEOFF MINIMUMS: **Rwy 15**, std. w/min. climb of 548' to 5100 or 3300-3 for climb in visual conditions. **Rwy 33**, std. w/min. climb of 355' to 6400 or 3300-3 for climb in visual conditions.

DEPARTURE PROCEDURE: **Rwy 15**, climb heading 147° to 6100 before proceeding on course. For climb in visual conditions, cross Jackson County airport at or above 6000 before proceeding on course. When executing VCOA, notify ATC prior to departure. **Rwy 33**, climb heading 327° to 6400 before proceeding on course. For climb in visual conditions, cross Jackson County airport at or above 6000 before proceeding on course.

When executing VCOA, notify ATC prior to departure. TAKEOFF OBSTACLE NOTES: **Rwy 15**, trees beginning 109' from DER, 31' left of centerline, up to 100' AGL/2939' MSL. Trees beginning 19' from DER, 53' right of centerline, up to 100' AGL/2859' MSL. Building 221' from DER, 324' left of centerline, 25' AGL/2864' MSL. Airplane on tarmac 137' from DER, 140' left of centerline, up to 20' AGL/2899' MSL. Transmission tower 1763' from DER, 860' right of centerline, up to 200' AGL/2879' MSL. **Rwy 33**, trees beginning 2' from DER, 182' left of centerline, up to 100' AGL/2979' MSL. Trees beginning 6' from DER, 27' right of centerline, up to 100' AGL/2979' MSL.

TARBORO, NC

TARBORO-EDGEcombe (ETC)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 93173 (FAA)

DEPARTURE PROCEDURE: **Rwy 27**, climb runway heading to 500 before turning.

UNION, SC

UNION COUNTY, TROY SHELTON FIELD

(35A)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 13234 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, trees beginning 1006' from DER, 20' right of centerline, up to 100' AGL/759' MSL. **Rwy 23**, trees beginning 2115' from DER, 20' left of centerline, up to 100' AGL/679' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

WADESBORO, NC

ANSON COUNTY-JEFF CLOUD FIELD

(AFP)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 2 11069 (FAA)

TAKEOFF MINIMUMS: **Rwy 16**, 400-2¼ or std. w/min. climb of 220' per NM to 800, or alternatively, with std. takeoff minimums and a normal 200' per NM climb gradient, TAKEOFF must occur no later than 1900' prior to DER.

TAKEOFF OBSTACLE NOTES: **Rwy 16**, trees beginning 64' from DER, 298' left of centerline, up to 70' AGL/359' MSL. Terrain beginning 112' from DER, 375' right of centerline, up to 0' AGL/311' MSL. Trees 1.8 NM from DER, 2732' left of centerline, up to 100' AGL/609' MSL. **Rwy 34**, trees beginning 722' from DER, 39' left of centerline, up to 84' AGL/403' MSL. Trees beginning 446' from DER, 9' right of centerline, up to 85' AGL/384' MSL.

WALLACE, NC

HENDERSON FIELD (ACZ)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 09071 (FAA)

TAKEOFF MINIMUMS: **Rwy 9**, 300-1 or std. w/ min. climb of 389' per NM to 400.

TAKEOFF OBSTACLE NOTES: **Rwy 9**, trees 2329' from DER, 462' left of centerline, 100' AGL/119' MSL. Pole 5056' from DER, 1074' left of centerline, 183' AGL/216' MSL. **Rwy 27**, vehicles on roadway 299' from DER, 421' right of centerline, 15' AGL/54' MSL. Trees 4916' from DER, 1296' left of centerline, 100' AGL/169' MSL.

WALNUT COVE, NC

MEADOW BROOK FIELD (N63)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 2 12320 (FAA)

TAKEOFF MINIMUMS: **Rwy 16**, 500-3 or std. w/ min. climb of 324' per NM to 2000. **Rwy 34**, 600-3 w/ min. climb of 229' per NM to 1400 or 1800-3 for climb in visual conditions.

DEPARTURE PROCEDURE: **Rwy 16**, climb heading 166° to 1400 before proceeding on course. **Rwy 34**, climb heading 001° to 2800 before turning West or for climb in visual conditions: cross Meadow Brook Field airport at or above 2300 before proceeding on course. When executing VCOA, notify ATC prior to departure.

TAKEOFF OBSTACLE NOTES: **Rwy 16**, vehicle on road 428' from DER, 591' left of centerline, up to 15' AGL/674' MSL. Trees beginning 541' from DER, 618' right of centerline, up to 65' AGL/804' MSL. Power line 2525' from DER, 226' right of centerline, 79' AGL/716' MSL. Tank 5738' from DER, 742' right of centerline, 157' AGL/863' MSL. Terrain 1.7 NM from DER, 2265' right of centerline, 999' MSL. **Rwy 34**, tree 1071' from DER, 517' right of centerline, 100' AGL/784' MSL. Trees beginning 1056' from DER, 844' left of centerline, up to 65' AGL/744' MSL. Trees 1.9 NM from DER, left and right of centerline, up to 100' AGL/1019' MSL.

17229

TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

WALTERBORO, SC

LOW COUNTRY RGNL (RBW)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 2 13122 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 5**, electrical system 28' from DER, 125' left of centerline, 3' AGL/103' MSL. Electrical system 29' from DER, 125' right of centerline, 2' AGL/102' MSL. Pole 139' from DER, 396' left of centerline, 4' AGL/105' MSL. Trees beginning 1787' from DER, 242' right of centerline, up to 54' AGL/158' MSL. Trees beginning 1903' from DER, 230' left of centerline, up to 54' AGL/186' MSL. Trees beginning 2898' from DER, 488' right of centerline, up to 75' AGL/196' MSL.

Rwy 9, terrain beginning 51' from DER, 195' left of centerline, up to 96' MSL. **Rwy 17**, trees beginning 1487' from DER, 441' right of centerline, up to 106' AGL/167' MSL. Tree 1579' from DER, 836' left of centerline, 117' AGL/176' MSL. **Rwy 23**, trees beginning 15' from DER, 499' right of centerline, up to 80' AGL/161' MSL. Trees beginning 1493' from DER, 10' right of centerline, up to 80' AGL/192' MSL. Trees beginning 1492' from DER, 15' left of centerline, up to 86' AGL/200' MSL. **Rwy 27**, tank 4946' from DER, 151' right of centerline, 140' AGL/219' MSL.

WASHINGTON, NC

WASHINGTON-WARREN (OCW)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1A 15260 (FAA)

TAKEOFF MINIMUMS: **Rwy 23**, 300-1 or std. with a min. climb of 250' per NM to 300.

DEPARTURE PROCEDURE: **Rwys 17, 29, 35**, climb runway heading to 400 before turning.

WAXHAW, NC

JAARS-TOWNSEND (N52)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 09071 (FAA)

TAKEOFF MINIMUMS: **Rwy 4**, 300-1 or std. w/ min. climb of 255' per NM to 900, or alternatively, with standard takeoff minimums and a normal 200'/NM climb gradient, takeoff must occur no later than 2200' prior to DER.

TAKEOFF OBSTACLE NOTES: **Rwy 4**, trees beginning 3' from DER, left and right of centerline, up to 100' AGL/759' MSL. **Rwy 22**, trees beginning 2' from DER, left and right of centerline, up to 100' AGL/709' MSL.

WHITEVILLE, NC

COLUMBUS COUNTY MUNI (CPC)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 09183 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 6**, trees beginning 2145' from DER, 553' right of centerline, up to 100' AGL/189' MSL. Trees beginning 2690' from DER, 838' left of centerline, up to 100' AGL/169' MSL. **Rwy 24**, trees beginning 1706' from DER, 831' right of centerline, up to 100' AGL/209' MSL. Trees beginning 732' from DER, 396' left of centerline, up to 100' AGL/209' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017


**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**


17229

WILLIAMSTON, NC

MARTIN COUNTY (MCZ)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 07214 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 3**, trees beginning 158' from DER, 98' right of centerline, up to 100' AGL/172' MSL. Trees beginning 3041' from DER, 168' left of centerline up to 100' AGL/172' MSL. **Rwy 21**, trees beginning 130' from DER, 57' right of centerline up to 100' AGL/168' MSL. Trees beginning 1393' from DER, 411' left of centerline up to 100' AGL/168' MSL. Vehicle on road 428' from DER, 15' AGL/80' MSL.

WILMINGTON, NC

WILMINGTON INTL (ILM)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 1 07130 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 6**, tree 2723' from DER, 558' left of centerline 57' AGL/90' MSL. Tree 3201' from DER, 401' right of centerline 73' AGL/110' MSL. Tree 3552' from DER, 643' right of centerline, 78' AGL/118' MSL. **Rwy 17**, multiple trees beginning 177' from DER, 438' right of centerline, up to 32' AGL/49' MSL. Tree 187' from DER, 545' left of centerline, 24' AGL/41' MSL. Multiple trees beginning 418' from DER, 540' left of centerline, up to 39' AGL/53' MSL. Tree 620' from DER, 246' left of centerline, 24' AGL/38' MSL. Tree 1468' from DER, 684' right of centerline, 66' AGL/83' MSL. Tree 1689' from DER, 592' right of centerline, 52' AGL/69' MSL. Transmission lines 3347' from DER, 1300' left to 1300' right of centerline, 135' AGL/160' MSL. **Rwy 24**, tree 163' from DER, 454' left of centerline, 61' AGL/75' MSL. Multiple trees beginning 1663' from DER, 277' left of centerline, up to 66' AGL/83' MSL. **Rwy 35**, tree 1500' from DER, 300' right of centerline, 50' AGL/83' MSL. Funnel 1796' from DER, 882' left of centerline, 57' AGL/90' MSL. Multiple trees beginning 1916' from DER, 138' right of centerline, up to 94' AGL/131' MSL. Multiple trees beginning 2486' from DER, 143' left of centerline, up to 107' AGL/140' MSL.

WILSON, NC

WILSON INDUSTRIAL AIR CENTER (W03)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 86296 (FAA)

DEPARTURE PROCEDURE: For departures 260° CW 320°: **Rwy 27**, climbing left turn to 2500 on heading 260° before proceeding on course. **Rwys 15, 21**, climbing right turn to 2500 on heading 260° before proceeding on course. **Rwys 3, 9, 33**, climbing left turn to 2500 on heading 320° before proceeding on course.

WINNSBORO, SC

FAIRFIELD COUNTY (FDW)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

ORIG 10322 (FAA)

TAKEOFF OBSTACLE NOTES: **Rwy 4**, trees beginning 46' from DER, 241' right of centerline, up to 32' AGL/588' MSL. Trees beginning 68' from DER, 261' left of centerline, up to 88' AGL/613' MSL. Trees beginning 517' from DER, 25' right of centerline, up to 100' AGL/640' MSL. Trees beginning 533' from DER, 23' left of centerline, up to 97' AGL/620' MSL. **Rwy 22**, poles beginning 70' from DER, 399' left of centerline, up to 46' AGL/624' MSL. Trees beginning 163' from DER, 43' left of centerline, up to 57' AGL/632' MSL. Pole 666' from DER, 436' right of centerline, 44' AGL/609' MSL. Trees beginning 708' from DER, 28' right of centerline, up to 68' AGL/633' MSL. Trees beginning 1528' from DER, 13' right of centerline, up to 87' AGL/645' MSL. Trees beginning 1597' from DER, 100' left of centerline, up to 111' AGL/669' MSL.

WINSTON-SALEM, NC

SMITH REYNOLDS (INT)

TAKEOFF MINIMUMS AND (OBSTACLE)

DEPARTURE PROCEDURES

AMDT 6 09015 (FAA)

TAKEOFF MINIMUMS: **Rwy 22**, 500-2¼ or std. with a min. climb of 330' per NM to 1600.

TAKEOFF OBSTACLE NOTES: **Rwy 4**, multiple trees beginning 1014' from DER, 159' left of centerline, up to 92' AGL/1041' MSL. Multiple trees beginning 2' from DER, 195' right of centerline, up to 62' AGL/1051' MSL. **Rwy 15**, bush and multiple trees beginning 109' from DER, 237' left of centerline, up to 81' AGL/960' MSL. Multiple trees beginning 123' from DER, 433' right of centerline, up to 66' AGL/945' MSL. **Rwy 22**, multiple trees beginning 376' from DER, 136' left of centerline, up to 65' AGL/1014' MSL. Antenna 4538' from DER, 1044' left of centerline, 189' AGL/1138' MSL. Tower 2.1 NM from DER, 2784' left of centerline, 468' AGL/1395' MSL. Antenna on building 2.3 NM from DER, 3230' left of centerline, 460' AGL/1376' MSL. **Rwy 33**, floodlight, multiple hangars, poles, and trees beginning 230' from DER, 41' left of centerline, up to 74' AGL/1083' MSL. Pole, windssock, multiple buildings and trees beginning 13' from DER, 141' right of centerline, up to 85' AGL/1084' MSL.

14 SEP 2017 to 12 OCT 2017

14 SEP 2017 to 12 OCT 2017

17229


**TAKEOFF MINIMUMS (OBSTACLE) DEPARTURE PROCEDURES, AND
DIVERSE VECTOR AREA (RADAR VECTORS)**
